

T:\Engineering\Traffic\Fiber\Projects for IS\32nd Ave Water Tower.dwg




32 AVE S

42 ST S

- ① F&I NEW 2" ORANGE HDPE DUCT, AND NEW DURATRACE LOCATE CABLE.
- ② REMOVE EXISTING PVC PULLBOX. F&I NEW CONCRETE POLYMER FIBER VAULT.
- ③ F&I NEW CONCRETE POLYMER FIBER VAULT.

702' NEW HDPE(INNERDUCT) WITH TRACER WIRE

WT



- Total quantities:
- 702' 2" Orange HDPE Conduit
 - 50' Must be Bored
 - 652' Can be plowed or bored
 - 2ea Concrete Polymer Vault
 - Approx 1000' of 12SM Fiber Cable

REVISIONS		
③	②	①
SEAL		
FIBER 32 Ave S Water Tower		
DESIGN BY: JJR	CHECKED BY: JMG	
DRAWN BY: JJR	ORIG DATE: 03/01/2019	
CITY OF Fargo	SECTION NO.	SHEET NO.
	160	3