SECTION 2800

CITY OF FARGO SPECIFICATIONS
GRAVEL SURFACING

PART 1
DESCRIPTION OF WORK

The work to be done under these Specifications shall include all labor, materials, accessories, and plant necessary to furnish and spread traffic surface gravel at the locations designated by the engineer.

PART 2
MATERIAL

2.1. MATERIAL (revised January, 2002)

Traffic surface gravel shall conform to the requirements of North Dakota Class 5.

2.2. EQUIPMENT

The scales shall be of the platform type sensitive to a weight of twenty pounds and shall have the capacity to weigh the maximum load. The scales shall be approved and calibrated by the state in which it is located and proof of such calibration furnished to the engineer upon his request. Each truck shall have a ticket showing it's weight and the weight of the gravel being hauled in decimal fractions of tons.

PART 3
CONSTRUCTION

3.1. SPOT LOCATION GRAVEL SURFACING

The contractor shall haul, deliver and spread the gravel at the location designated by the engineer. The aggregate shall be deposited, spread, and shaped to conform to the required grade.

3.2. GRAVEL SURFACING ON GRAVEL SURFACING PROJECTS

The contractor shall haul, deliver and spread-dump the gravel to the approximate depth required. The engineer will furnish a man to direct the trucks where to dump and to take tickets. The contractor shall furnish a maintainer blade and operator on these type projects to grade and compact the gravel to the desired depth and density. The aggregate shall be deposited, spread and shaped so the moist compacted gravel will be tightly bound, smooth and uniform.

PART 4

GUARANTEE, MEASUREMENT & PAYMENT

4.1. GUARANTEE

There is no guarantee required on these type projects.

4.2. MEASUREMENT AND PAYMENT

The cost of the traffic surface gravel shall be paid for at the contract unit bid price per ton.