


STORMWATER
MANAGEMENT
PROGRAM

2023 ANNUAL
DISCHARGE
MONITORING
REPORT



PREPARED BY
Peggy Amsbaugh
Engineer Tech. III



Introduction and Description

The 2023 Discharge Monitoring Report is given in a format in conjunction with the NDR04-0000 permit. Presented sequentially to follow the permit elements, the report begins with general requirements and progresses through the six Minimum Control Measures. Highlighted or example documentation is provided at the end of each section as appropriate. A growing number of resources are digital or linked to AutoCAD/GIS, which is available for audit upon request.

The **Fargo MS4 Compliance Summary** is a matrix of Part V of the NDR04. This table illustrates compliance responses spanning each control measure and the MS4 Program overall in abridged exhibits. Please see each separate measure for topic specific criteria responses.

Evaluation and Assessment

Evaluation, assessment and effectiveness of goals, projects and BMPs is conducted annually. Fargo's MS4 Program meets compliance goals set locally and by the state NDR04 permit requirements. Results of these measures and recommended changes are consolidated on a summary sheet (MS4 Compliance Summary) at the end of this section.

MS4 Program Map

Fargo perpetually maintains a state-of-the-art geographic information system (GIS) and AutoCAD mapping program of the complete infrastructure system (permit items IV.E.a-f). These platforms calculate all property areas and components of the municipal systems. This map is available for viewing at the office but is unavailable for outside access due to security concerns.

MS4 Operated Facilities

Fargo Wastewater and Solid Waste entities operate under separate stormwater permits. Please contact each department for their specific permit requirements.

Pollution Assessment (Identified Pollutants)

Fargo has identified pollutants and specifically lists them in the Stormwater Ordinance (Chapter 37 of the City of Fargo Municipal Code). The ordinance lists obvious water degrading agents or practices, but it also states that any action or process that diminishes water quality is a violation. Stopping or reducing negative discharge is the goal of not only the regulation, it is the essence of the entire stormwater program.

Reduction/removal of these pollutants is accomplished by structural (retention, detention ponds, grit chambers, etc.) and non-structural (prescribed discharge rates, compliance practices, etc.) BMPs.

Public Availability

This report is made available to the public online at: [The City of Fargo - Storm Water Management](#)
The MS4 program and related operational documents are available upon request during business hours.

The screenshot shows the City of Fargo website's page for the Storm Water Management Program. The header includes the City of Fargo logo, navigation menus for 'Live', 'Work', 'Explore', 'City & Government', and 'News & Events', and a search bar. The main content area features a blue sidebar with a 'Fargo ENGINEERING' logo and a list of navigation links: Traffic Engineering, Storm Sewer Utilities (with sub-links for Service Charge, Maintenance, and Management), Storm Sewer Design & Construction, Engineering Services, Flooding & Flood Control, Design & Construction, Special Assessments, Calendar of Events, Contact Us, and FAQs. The main content area is titled 'Storm Water Management Program' and includes a brief description of the program's goal, a list of six minimum control measures, and contact information for the Engineering Department. A 'Resources' section lists various documents and reports available for download.

THE CITY OF Fargo
FAR MORE

Translate Text Size Search...

Live Work Explore City & Government News & Events

THE CITY OF Fargo
ENGINEERING

Home > City & Government > Departments > Engineering > Storm Sewer Utilities > Storm Water Management

Storm Water Management Program

The goal of the Storm Water Management Program is to protect the bodies of water that receive storm water from the City of Fargo. This is accomplished by minimizing the pollutants discharged from the municipal storm sewer system into the Red River.

This program consists of six minimum control measures:

- Public Education and Outreach
- Public Participation and Involvement
- Illicit Discharge Detection and Elimination
- Construction Site Storm Water Runoff Control
- Post-Construction Storm Water Management
- Pollution Prevention and Best Management Practices (BMP)

For more information or to comment, contact the City via the Contact Information section in the right margin of this page.

Resources:

- Policy on Storm Water Discharge and Treatment Requirements - Rev. April 2023 (PDF)
- 2022 Annual Storm Water Report (PDF)
- Storm Water Permits
- City Storm Water Ordinance
- Homeowner Fact Sheet for Erosion & Sediment Control
- Homebuilder Guidelines for Erosion & Sediment Control
- Flood and Stormwater Fact Sheet

Contact Information

Engineering Department
223 4th Street North
Fargo, ND 58102
[Get Directions](#)
701.241.1545

Shared Program Agreements with other MS4s

The City of Fargo and North Dakota State University have an agreement that the city performs construction permitting and inspection on campus. NDSU is responsible for all other reporting elements in the permit.

Table of Contents

Narrative

General Requirements Support Material

Minimum Control Measure 1 (MCM-1)

Minimum Control Measure 2 (MCM-2)

Minimum Control Measure 3 (MCM-3)

Minimum Control Measure 4 (MCM-4)

Minimum Control Measure 5 (MCM-5)

Minimum Control Measure 6 (MCM-6)



Fargo MS4 Compliance Summary

	(NDR04-V.c.1) Permit Status Compliance: BMP Assessment & Evaluation	(NDR04.V.c.2, 3) Measurable Goals Compliance, Progress, Completed	City of Fargo MS4 Compliance Summary	(NDR04-V.c.5) Future Planned Activities	(NDR04-V.c.6) Changes to BMP or Measurable Goals	(NDR04-V.c.7,8) Responsible Entity	(NDR04-V.c.9) Violations Issued	Reviewed
MS4 Program Overall	Complies, BMPs adequate	All MCM Goals meet compliance and were completed.	Fargo's MS4 Program is effective in addressing & reducing non-compliant discharges.	Additional studies, new reporting capabilities may enhance or expand goals.	No changes are planned for 2023 beyond the studies.	Fargo Storm Sewer Utility	2-12-24	See individual Minimum control Measures for detailed information and supporting documentation.
MCM-1 & 2	Complies	Completed	Effective	Maintain As-is	No Changes	SSU	2-12-24	Most information in the report is available online www.FargoND.gov/city-government/departments/engineering/storm-sewer-utility/stormwatermanagement
MCM-3	Complies	Completed	Effective	Maintain As-is	No Changes	SSU	2-21-24	
MCM-4	Complies	Completed	Effective	Maintain As-is	No Changes	SSU	2-22-24	
MCM-5	Complies	Completed	Effective	Maintain As-is	No Changes	SSU	2-26-24	
MCM-6	Complies	Completed.	Effective	Maintain As-is	No Changes	SSU	2-26-24	

138
 (Excludes Environmental Health and Wastewater Treatment Departments)

MCM 1 & 2

Stormwater Education Program




Involvement

Outreach

Participation



MCM 1&2 Education, Outreach & Involvement

Audience	Pollutant (group)	Goals	Activities	Messages	Implementation/ Schedule	Entity	Performance Measures	Adjustment Method	Reviewed	Modification Recommendations
Construction	A, C, D	Acquired skill/behavior change	Problem-based learning <ul style="list-style-type: none"> On-site evaluation Classroom instruction 	<ul style="list-style-type: none"> Specific construction related Use BMPs to reduce soil & trash migration Contain chemicals/lubricants Reduce other negative impacts 	Annual, continuous during construction season		<ul style="list-style-type: none"> Participation count Permit/violation report Complaint log Staff referral Maintenance record 	<ul style="list-style-type: none"> Yearly program review Direct contact Verbal interaction with partners, other agencies and facilitators 	2/20/2024	Continue to improve annual spring Stormwater Conference
General Public	A, C	Awareness	Inquiry-based learning <ul style="list-style-type: none"> Classroom instruction River Keepers programming Fact sheet/newsletter Demonstrations Billboard 	<ul style="list-style-type: none"> Your actions impact stormwater Reduce water quality degrading practices Report illicit (prohibited) discharges 	Continuous, seasonal		<ul style="list-style-type: none"> Participation count Permit/violation report Complaint log Staff referral Maintenance record 	<ul style="list-style-type: none"> Yearly program review Direct contact Verbal interaction with partners, other agencies and facilitators 	2/20/2024	Continue water quality device & retention ponds log and inspections
Municipal Operations	A, C, D	Acquired Skill	Project-based learning <ul style="list-style-type: none"> Training video Presentation 	<ul style="list-style-type: none"> Municipal operations impact stormwater Water quality degrading observations Report illicit (prohibited) discharges 	Annual rotating basis, some departments may also provide in-house training		<ul style="list-style-type: none"> Participation count Permit/violation report Complaint log Staff referral Maintenance record 	<ul style="list-style-type: none"> Yearly program review Direct contact Verbal interaction with partners, other agencies and facilitators 	2/22/2024	Continue accurate reporting and recording between Public Works Superintendent and SSU staff

Minimum Control Measures 1 & 2

Fargo's Stormwater Education Program

In summary, the MS4 Permit Minimum Control Measures (MCM) 1 & 2 require the city to provide education, outreach, public participation and involvement opportunities. We must specifically address construction and post-construction pollution prevention, illicit discharges and methods to reduce negative discharges, while conducting our municipal operations. Additionally, we must develop a method to quantify our educational effectiveness and provide a method to adjust the programming.



Our education program integrates the requirements prescribed under these MCMs. Collectively, the Fargo Stormwater Education Program uses a “based” learning approach to educate, inform and involve people concerning Stormwater’s impact on water quality. Although water quality is not a new concept today, polluting agents and practices might not be obvious in people’s minds. Our program helps inform the public about water polluting practices and what they can do to reduce or eliminate them. Learning and participation is focused toward target audiences and utilizes a variety of activities, projects, methods and mediums to educate and inform people about stormwater and water quality.

We have specifically designated construction, municipal maintenance operations and the “public” as our target audiences. The targets were selected based on perceived need, impact potential, MS4 requirements and the ability to deliver programming. Learning delivery to these segments is scheduled and consists of direct or implied, activities, projects or techniques. For instance, consider that soil migration is of primary concern at a construction site, yet it also occurs at a flower bed. Where a construction site has specific Best Management Practices (BMPs) that must be utilized, an implied concept of awareness (that soils migrate) may be adequate to the flower bed scenario. Education may be a simple billboard message (Inquiry Based) or specific technical training (Problem Based), depending on the audience or practice.

How we measure the education program’s effectiveness is yet another challenge. Quantification is one method. We simply count people participating in training seminars, providing feedback or the number of projects delivered (fact sheet or other), violations issued, sediment or trash removed, etc. The following pages highlight our program’s architecture, complete with illustration tables, graphics, images and examples of the actual materials utilized in the delivery of the program. The final section is focused on program performance measures (evaluation) and adjustment methodology.

Fargo's Storm Sewer Utility Staff

Our staff conducts related environmental education and outreach learning activities along with other City staff, core partners and related entities. The concept of water quality in stormwater discharge is the goal of the education, involvement and participation programming.

Facilitators

- The City of Fargo Storm Sewer Utility (SSU) is responsible for the Stormwater Program's administration.
- Contributors include City departments: Environmental Health, Solid Waste, Public Works and Water Reclamation.
- Fargo River Keepers is a core partner promoting stormwater/ecology education to the general public. Classroom instruction, lab activities and public involvement/participation projects comprise their basic curriculum.
- Other entities delivering similar educational programming include: Red River Basin Commission, local watershed districts, Cass County Soil Conservation, Homebuilders of Fargo/Moorhead etc and NASECA North Dakota.



Example of contribution by other facilitators

The City of Fargo recycling coordinator delivers programming themed toward the concept that recycling reduces environmental impact and promotes water quality.

Recycling Education



Pollutants and Best Management Practices

Fargo has identified pollutants and specifically lists them in Chapter 37 (Stormwater Ordinance). The ordinance lists obvious water degrading agents or practices but, it also implies that any action or process that diminishes water quality is a violation. Stopping or reducing negative discharge is the goal of not only the regulation, it is the essence of the entire stormwater program.

Knowing or identifying a pollutant is the first important aspect of our stormwater program. The second most important item is simply stopping or reducing the effect of the pollutant before it reaches a storm sewer inlet and eventually the river. This stopping or reducing (whatever it might be) is called a Best Management Practice or BMP. It could be a mat or fiber roll between the street and a stripped construction site or stopping watering before any sediment/dirt from a flowerbed is carried into the street gutter.

Activities and Methods Used to Deliver our Program

Mass Marketing




Digital Media


- Website www.FargoND.gov (Far More On Demand)
- Twitter
- Facebook



Far More On Demand



Direct Mail & Factsheets



Core Partners



River Keepers delivers water ecology education, and provides volunteer opportunities for the general public. Their mission is to advocate sustainable use of the Red River of the North, primarily within the Fargo-Moorhead area promoting a renewed vision. River Keepers is dedicated to educating our community by increasing local watershed knowledge through active engagement.

River Keepers Activities

Activities include the annual Red River Water Festival, backpack program, geocache, interpretive signs, storm drain marking program and river friendly house and yard management. Fargo SSU staff participates with River Keepers in various activities annually.

The Red River Water Festival sponsored by River Keepers is a very popular annual ecology program for area fourth grade students. This learning event brings students to the river, where they learn and participate in water quality concepts. SSU staff participates with teaching and providing funding.



Committees

- Conservation
- Forestry Advisory

Feedback



Stormwater@FargoND.gov

Community Feedback

The opportunity to provide feedback on stormwater topics is communicated in various activities and projects. Community feedback is managed citywide on a unified basis through a number of portals including office visits, mail, telephone, website, email, Engage Fargo and FargoOne.

Performance Measures

How do we evaluate the effectiveness of our MCM 1 & 2 programming since quantification is so difficult to apply. Some of the methods are listed below, others must be intrinsically interpreted by staff. An increase of incident reports by the public in 2023 is directly related to the increase of awareness of these degrading pollutants.

- Counting (attendance, address mailings, contact log, complaint log, frequency of Learning opportunities, etc.)
- Feedback from electronic reporting portals (email, FargoOne, etc.)
- Inter-department communication (increased - trash, sweeping, pipe cleaning, etc.)
- 2023 awareness incident reports

Program Adjustments


Annually (usually in the first two months of the year), all MCM programming is analyzed. Constructive input from the program's targeted sectors is evaluated by the Fargo Storm Sewer Utility staff. Changes (additions or deletions) are incorporated and carried out.

Current program is deemed adequate and no changes are recommended for 2024. MCM 1 & 2 contributions will be maintained at the existing level.

Public Involvement & Outreach Map - 2023

Legend

-  Red River Water Festival
-  Fargo City Hall
-  River Keepers
-  Fargo Cass Public Health
-  Billboard Location
-  HBA



2023 Public Education

January – Recycle Right Campaign with AE2S that included social media posts, messages and games.

February – Recycle Right Campaign continued with facts and recycling guidelines.

March – No Glass in the curbside bins education that included radio interviews, face book videos, post cards to all residents. Also presented to 60 students at Longfellow Elementary on the three R's.

April – Hosted the annual Earth Day Poster Contest at Jefferson Elementary, winning poster went on a billboard in Fargo.

May – Multiple Clean up Week interviews and videos during the 2 week span and also presented to 60 children at a local daycare.


June – City of Fargo / SWANA Hauler Outreach and Safety Event held at the Fargo Landfill in conjunction with Sanitation Products. Spoke with each driver that crossed the scale, gave safety reminders, a flyer and food/drink.

October – Partnered with Minnkota Recycling to host the Cans for Cash program, raising funds for the Got No Milk program at Fargo Public Schools, with the funds donated on Giving Hearts Day so 1,910 cartons of milk were donated.

We also did four live promo interviews with WDAY covering topics like battery fires in recycling, proper aerosol handling, commercial recycling and yard waste.

November – Celebrated America Recycles Day with radio interviews raising awareness on recycling issues and thanked our commercial recycling customers for making a difference.

Red River Water Festival Outdoor Map



KEY:

1—Blue River

2 —Trees the Water Keepers (position so the canopy does not cause a visibility hazard for bikers)

3 —River Crime Lab

4—Incredible Journey

5— Stream Sense

6—Invaders!

 - Porta potty



💧 Dates

The Red River Water Festival is scheduled for September 19-22, 25-27.

💧 Location

Hjemkomst Center, 202 1st Avenue North in Moorhead

Outside stations/canopies will be in Viking Ship Park: to the west of the Hjemkomst Center. Be aware that there is a porta potty behind the Rental Shack in the parking lot and a First Aid Kit at Canopy 1.

Inside stations: The floors are opposite of what you think. Gallery 4 is the very bottom level! Be aware that there is a First Aid Kit at the Snack Bar.

💧 Weather

Outside activities will be held rain or shine. **Dress in layers and come prepared for the weather.** In the event of lightning, we will move the activities inside. The back up locations for indoors are listed in parentheses on the schedules.

💧 Shift Schedule

Arrive at least 15 minutes prior to the beginning of the shift to make sure your activity is set up as you wish.

Check in with me in the Snack Bar area or text me at 701.306.6181 when you arrive so we know we are ready for students.

Outside activity leaders:

- At the beginning of your shift, you will need to set up your activity.
- At the end of the day, please pack it back up and leave it on the table. Please have the students stack the buckets,

There are four rotations each shift that look like this:

- There are **21 minutes for the activity.** Please make sure you get to the **activity** portion and not just present as that is why the schools attend the water festival.
 - A timer volunteer will use hand signals to communicate with you. They will give you a **'high five'** to let you know **when you have 5 minutes left to wrap up the activity.**



- Next the timer volunteer will signal with 4 fingers to let you know **it is time to journal**. Give the 1st teacher in your shift the bag of goodies on the table which will include their journals. They need to take this bag with them to the other stations.



- Each activity station will have an **Activity Station Box** which contains markers, paper, tape, hand sanitizer etc. for you to utilize as you wish. They also contain a **pencil sharpener and pencils**. **Please gather the pencils from each class before they rotate** to the next activity.
- **Please help them answer the following journal questions:**
 - Station Name
 - What did you do at this station? List two things that you learned.
 - What new words did you learn?
 - What would you like to learn more about?

- Finally, the timer volunteer will signal with a pointer finger going in a circle to let you know **the class should rotate to the next activity**. Do **NOT** dismiss the class early. This is done so that movement by one class does not disturb another activity in session.



💧 **Lunch, Snacks and Beverages**

There will be a light lunch between sessions on the 19th and 20th which will be served on the Snack Bar counter spaces inside the Hjemkomst Center. Volunteers should not go into the kitchen area as not everything in the kitchen belongs to River Keepers. Since there are no afternoon sessions the rest of festival, we will just have snacks you can grab before or after your shift.

💧 **Major Sponsors**

ND Project WET, Xcel Energy, City of Fargo and City of Moorhead

If you have any further questions about the Red River Water Festival, call me at 701.235.2895 or e-mail me at christine@riverkeepers.org. If you need to get a hold of me the week of the water festival, my cell phone number is 701.306.6181.

Thank you again for helping with this fun educational event!

Christine C Holland

Christine Holland
Executive Director

WHAT IS A STORM DRAIN?

Storm drains are the grated openings in the street that collect water from rain and melting snow to minimize street flooding.

As stormwater flows along streets, it collects trash, leaves, grass clippings, pet waste, car fuels and other pollutants into storm drains.

Pesticides, paints, antifreeze, and other used motor oil can end up in the storm drains when people dispose of them improperly. This is an illicit discharge and is against city ordinances.



WHAT CAN YOU DO?

- Volunteer to mark storm drains to teach others about stormwater
- Prevent pollution by keeping contaminants out of storm drains
- Follow the No Dumping Drains to River message and do your part to help protect our water
- Sign up your volunteer group to mark storm drains by contacting River Keepers



A volunteer program to protect the Red River by linking human actions to pollution problems.

WHAT IS THE PROBLEM?

Have you ever wondered where water goes after it 'disappears' into a storm drain? Stormwater in Fargo-Moorhead is not treated at a wastewater plant, but is discharged directly into the Red River or Sheyenne River through outfall pipes. Runoff carries contaminant and debris picked up along the way, polluting our surface and groundwater, which are often drinking water sources.



CONTACT US

River Keepers
kimberly@riverkeepers.org
701.356.8915
riverkeepers.org
1120 28th Ave. N., Ste. B
Fargo, ND 58102

ADDITIONAL INFORMATION

riverkeepers.org
FargoND.gov
cityofmoorhead.com
westfargond.gov

THE CITY OF
Fargo
FAR MORE



PREPARATION

1. Discuss the storm drain marking program with your youth group, school class, civic organization, family, neighborhood group or friends. It is recommended that participants be at least 10 years old.
2. Select a date for marking. The pavement must be dry and the weather must be above 50 degrees.
3. Choose a time of day and length of time available to do the project. Two hours is the recommended length.
4. Select a neighborhood to mark and a location to meet.
5. Figure out the number of participants.
6. Recruit supervisors. One supervisor is recommended for every 4-8 youth volunteers, depending on the age.
7. Plan an alternative date in case of rain.
8. Contact River Keepers to set up the project, which includes supplies and training.

DAY OF PROJECT

Review the following instructions with participants or scan the QR code to watch a training video (available on our YouTube channel).




Put on safety vests.

Break into groups - two people to mark the curb, two people to distribute door hangers.

CURB MARKING TEAM

1. Decide where to put the marker.
 - Surface must be flat, dry, and make contact with the whole marker. The preferred placement is on top of the curb.



- The second option is on the face of the curb.
- If the curb is not possible, the street right next to the curb and storm drain is the last option.



2. Sweep the area where the marker will be placed so it is free of any loose debris.
3. Peel backing paper off one side of the adhesive disk.
4. Place storm drain marker evenly on top of the adhesive disk.
5. Remove backing paper on other side of the adhesive disk.
6. Apply to cleaned area. It is important that the entire edge of the marker is sealed to the curb or street.
7. Step or place pressure on the storm drain marker to make sure the adhesive sticks.

DOOR HANGER TEAM

- Walk on sidewalks, stay off of the grass.
- Do NOT put door hangers in mailboxes.
- Place door hanger on the door that looks most used. Do NOT open the door.
- Do NOT leave a door hanger if it will blow away.



FOLLOW-UP

- Indicate streets marked on maps provided.
- Document how many volunteers participated and how many hours were volunteered.
- Return maps and extra storm drain marking supplies.
- Congratulate yourselves...you deserve it!



MCM 3 – Illicit Discharge Detection and Elimination (IDDE) Program

Degrading water quality (Illicit Discharge) by dumping substances or bypassing the sanitary system is illegal. The Red and Sheyenne Rivers are the source of the City’s water supply, so protection of our drinking water is a critical mission. In response to that charge, the City has created a detection and elimination program commonly known in the stormwater world as the IDDE Program.

Fargo’s IDDE Program uses the same design as many other MS4 entities. Public education/ involvement/awareness along with training municipal staff are key components of the program. Specifically, the IDDE Program’s focus is on the discovery, containment and elimination (mitigation) of water degrading practices. There are a number of rules and procedures available in the city to address non-conforming discharges.

In addition to State and Federal regulation, the Stormwater Ordinance defines non-conforming and allowable discharge that can enter our storm sewer utility. Construction and land disturbing activities are addressed as. Dumping any adverse substance in any form is a violation. Fargo’s Stormwater Management Program under supervision of the Fargo City Engineer administers enforcement along with the full support of other city departments.

IDDE Spill Response




Illegal discharge reports

Illegal discharge reports communicated by other staff or the public follow the standard operating procedure format. Administration is by the department responsible for a particular operational

segment. For example, reports involving a restaurant dumping grease into the sewer or on the ground is referred to Fargo Cass Public Health – food inspection division. Suspect illegal non-functioning storm sewer connection or infiltration routes to public works for remedy or testing. All hazardous material exposure incidents are directed to the Fargo Fire Department’s HAZMAT Team. Each of these departments would take the lead command of operations and the Storm Sewer Utility Department reverts to a support role.

Illicit Discharge & Elimination Map – 2023

- 45 St/19 Ave N
- 140 40 St S Lunde
- 501 21 St N
- 737 2 St N
- 902 12 St N
- 3225 12 Ave N
- 4350 Main Ave
- 5509 19 St S
- Robert Kantola



Routine Municipal Operations

Non-conforming material is an everyday maintenance issue for Fargo’s Public Works (FPW) operations group. Operational staff is the field staff, defined by job description directed toward maintenance tasks of the city. Department staff vary from garbage pickup to snowplow route operators who are out patrolling the city constantly. All staff are trained to report operational inconsistencies including illicit discharge due to spill or other circumstance.

Education, outreach and involvement

Education and outreach on this topic is conducted in concert with MCM 1 & 2. In all contact situations the perpetrator is appropriately educated concerning mitigation resolution along with any penalties assessed. Factsheets or violations are also used to educate the public and business operations on illegal dumping and other storm water conflict situations. Directed informational topic pieces like a fact sheet or letter is customarily sent to a geographic or similar group of people if a primary perpetrator cannot be identified. City staff is also trained for IDDE specific exposure in conjunction with MCM 6 (municipal maintenance operations).



Fargo IDDE Program Components

- Chapter 37 (Stormwater Ordinance available online www.FargoND.gov/auditors)
- Illicit discharge detection & elimination standard operating procedure
- Illicit discharge detection & elimination Work Order
- Educational Support Material
- Notice of Violation
- Drainage Complaint Log

Quantification, Appropriateness and Program Recommendations

There are multiple incidents of illicit discharges reported annually to various departments. Each department mounted a suitable response and if appropriate performed necessary mitigation action to reduce future replication. Documentation of such incidents is perpetually maintained in department records. This system is highly functional, with no operational changes recommended.



Illicit Discharge Detection and Elimination (IDDE)

Standard Operating Procedure for IDDE

Staff assess the site situation and determines the best course of action. Staff's goal is to respond to a report of an illicit discharge in a timely manner, aid in its termination and enable remediation.

Field staff is trained how to spot an illicit discharge and report it for further investigation.

Site Investigation

Assess the situation –

- Visual inspection of the site.
 - If life or property is at immediate risk call 911
 - If it can be done safely, stop the source of the spill
 - Take pictures/notes: location, size, colors, odors, type of material, etc.
 - Make contact with property owner/manager and direct to mitigate.
 - Contact appropriate department that oversees segment

Contacts

- Fargo Fire Department 911 (non-emergency 241-1540)
- Environmental Health 476-6729
- Street Department 241-1453
- Water Reclamation Plant 241-1445

Enforcement

- Issue Notice of Violation or Administrative Order to the violating party
- City also may charge owner for contractor/department site clean -up
- Non-compliance or post mitigation effort may be referred to City Prosecutor

Report Log

Keep a log of illicit discharges, response and mitigation.


Post remediation inspection

Perform site inspection to ensure mediation/mitigation was conducted.



Illicit Discharge Detection and Elimination (IDDE)

Standard Operating Procedure
(NDR04, Part IV.F.3b)
Typical procedures but others may apply.



Storm Sewer Utility takes a support role to lead department.

Site re-inspection conducted post response.

- If no or insufficient mitigation is accomplished, administrative order to correct is issued.
- Municipal Court

MS4 Underground Tank Storage Policy

General Description

The classification, Underground Storage Tank (UST), also UST Systems is divided into two categories Regulated and Unregulated. USTs are normally associated with fueling (gas) stations, petroleum distributors or commercial/industrial operations and some residential sites. Locally the City of Fargo has three departments affiliated with USTs, fire, health and storm sewer. See description of departmental interaction below.

Regulated USTs are controlled by the State of North Dakota's Environmental Quality Division under their UST Program. NDCC Chapter 33-24-08 Technical standards and corrective actions requirements for owners and operators of underground storage tanks.

Unregulated UST remain under local observation with FFD having permit and location mapping authority, FCPH-EH assists in tank removal operations and health risk discoveries. The Storm Sewer Utility functions in a support role whenever a potential for release into the storm utility system.

Fargo Fire Department

- Permits installation, piping & inspects sites.
- Maintains UST database (location map)

Fargo Cass Public Health's Environmental Division

- Removal of buried tanks
- Records & forwards UST health risks to ND

Storm Sewer Utility (MS4)

- Cross-contamination into STS (with FFD, EH & PW)
- Discharge/Spills into STS
- Works in support of FFD & EH
- Most instances of release trigger the Illicit Discharge Detection and Elimination Program (IDDE) protocol (HazMat)

Notice of Stormwater Violation

Owner/Operator

Construction Site Address

Contact Fax #

Date/Time

The Owner/Operator of this site shall correct the site's deficiencies listed below within **48 HOURS FROM DATE POSTED**

Permit #

A re-inspection for site compliance will occur 48 hours after violation issuance¹.

CONFIRM RECEIPT IMMEDIATELY AT: stormwater@FargoND.gov or FAX: 701.241.8101

Site Deficiency Violations

Corrective Action Required:

- BMP's Not Placed or Maintained
- Grass Buffer Strip Compromised
- Illegal Temporary Entrance
- Illegal Discharge²
- Inlet Protection
- No ESC Permit
- Street Tracking³
- Other:

Additional Enforcement Action

1. If non-conforming conditions exist upon re-inspection, the owner, operator, or permit holder shall be subject to a re-inspection fee of \$60/hr (\$30 minimum). **Failure to correct may also result in prosecution under the Fargo Municipal Code (with penalty not to exceed \$500.00).**
2. A live, illegal discharge is grounds for the immediate issuance of a **Stop Work Order**.
3. Tracking onto City streets can, at any time, result in a citation and **Summons to Appear** under Section 11-0901 of the Fargo Municipal Code.

Re-Inspection Fee

Date & Fee

Date & Fee

Date Referred to City Attorney

Date Referred to State of ND

TOTAL

Owner/Operator: Sign & FAX to 701.241.8101

Issued By:

2023 Drainage Concern Field

Number	Date	Name	Address	Concern	Action
1	4/18/23	L. Richard	2205 99 Ave S	Wants to build on Wild Rice River lot	sent letter explaining the process steps
2	4/19/23	Tim Blaufuss	3419 Bohnet Blvd N	Drainage issue	The individual made request for callback but did not answer or return my call
3	5/3/23	City of Fargo	52nd Ave N SW Corner of lagoons	Culvert failure	Hire Dirt Dynamics to remove and replace
4	5/3/23	Essentia lot	32 Ave S & 33 Ave S	Behind Arco, pond structure sink hole	Essentia to hire contractor to repair structure & backfill hole
5	5/10/23	Lori McDonald	6665 28 St S	rear yard drainage	Kevin worked with Jordahl to fix drainage along levee
6	5/10/23	City of Fargo	26 Ave S & 33 St S	sink hole next to storm sewer structure	Hire Master to make repairs
7	5/11/23	Chad Bolte	2797 69 Ave S	rear yard drainage	provide rear yard grades
8	5/12/23	Don Sayler	1106 24 Ave S	rear yard drainage	provided stakes to grade along fence to inlet
9	5/25/23	Josh Swanson	2313 26 1/2 Ct S	drainage along north property line	provided stakes to grade along fence to inlet
10	5/25/23	Richard Johnson	7902 Aquarius Dr	new house blocking drainage	homebuilder on 7816 15 St S and their engineer Houstin to handle
11	5/25/23	Mary Ann Dockter	5216 17 St S	Ditch doesn't drain	prop in ET and has open ditches, soln is to urbanize and add storm sewer
12	6/5/23	Travis Kjelshus	2925 35 1/2 Ct Ave S	rear yard inlet sink hole	Mike-Public Works to have crew repair
13	6/7/23	Public Works	40 Ave S & 38 St S	sink hole by sidewalk	Corey-Public Works to fill hole and monitor
14	6/12/23		3393 Jefferson St S	grass growth on boulevard	Project UR-20-A1 inlet repair re-seeded but home owner didn't water
15	6/13/23	Mike Snelgrove-Butler Machinery	3401 33 St S	drainage	Butler regrade their ditch and right of way ditch to drain better
16	6/15/23	Public Works	19 Ave N & 18 St N	settlement next to inlet in 19 Ave N	Border States repaired inlet and patched street
17	6/23/23	Steve Zaiser	802 7 St S	Intersection drainage	Public Works Jet inlet and video storm pipe
18	6/29/23	All Finish	4201 14 Ave N	Existing Inlet	re-align curb and gutter to drain to inlet
19	7/5/23	Public Works	52 Ave S @ Dr 27	settlement on Storm pipe next to path	will add to 2024 repair project & fence for now
20	7/6/23	complaint call into FargoCass Public	2302 18 St S	drainage complaint	private inlet, property manager know
21	7/19/23	call in no name	2702 1 Ave N	mud in inlet blocking drainage	Met Wade Dirt Dynamics street and inlet clean couldn't find a problem
22	7/19/23	call in no name	429 21 St S	drainage along new path complaint	Notified Park and engr MBN
23	7/20/23	call in no name	2871 Umber Ct	homeowner wants to move tree into pond lot	talked to Sam @ park need to stay away from pond with tree
24	7/25/23	Public Works	57 St N & 14 Ave N	slope erosion by pond	notified adjacent utility to remedy drainage and repair erosion
25	8/9/23	Janet Jones	6827 Crofton Lane	wants to put fence on pond easement	told her she couldn't put fence on pond easement
26	8/10/23	daycare next to pond	4248 32 Ave S detention pond	smell, muskrats, garbage	private pond notified owner to clean up
27	8/15/23	homeowner complaint	3590 Harrison St S	flooding in curb across driveway	checked inlet & clean, appears to be isolated rain event cause temp flooding
28	8/18/23	Justin Mezenga	3700 49 St S	rear yard drainage	need to grade yard to drain to inlet
29	8/25/23	Damon Balsdon	63rd St S & 54 Ave S	curb drainage	curb drains slow/future street project look at larger drainage work
30	9/6/23	Sarah Anderson	3712 Taylor St	backyard drainage	need to get neighbors to agree to survey & to drainage repair, lots of fences
31	9/18/23	property owner commercial	3433 Fiechtner Dr	low area rear yard	ok to fill but maintain rear yard drainage with neighbors
32	10/9/23	Ron Kerber	1201/1242 32 Ave N	repeat-side yard drainage	told him it's a private issue with neighbor apartments
33	10/10/23	Schmidts Jewelry/Brenda Giere	3241 42 St S	sidewalk heave next to sanitary manhole	add to 2024 sidewalk repair project-notified Brandon B
34	10/26/23	Paul	3826 3 Ave N	driveway drainage	private property issue
35	11/9/23	call in no name	7102 & 7106 12 St S	ET flood plain issue	any new residential buildings BFE + 4', garage BFE + 3'
36					
37					
38					
39					
40					
41					
42					
43					
44					



2023 Log of Walk-in the Office, Site Visit, Telephone and Email FIRM Information provided by Fargo CFM Employees

Type
 E - Email = written text communication, English Language (EL)
 O - Office = in-person, told verbal communication (EL)
 P - Phone = told verbal communication, (EL)
 S - Site visit
 Z - Stormwater

MI1 - Basic FIRM Information
 MI2 - Additional FIRM Information
 MI3 - Problems not show on FIRM
 MI4 - Flood Depth Data
 MI5 - Special Flood Related Hazard
 MI6 - Historical Flood Information
 MI7 - Natural Floodplain Functions

A requirement of CRS Activity 320 & 360

Date	Type	Address	Contact Name	Panel	Zone/BFE	Depth of BFE	Information Given	Past flood Repetitive Loss Area	Gave Flood Insurance Info	Action / Findings / Outcome / Recommendations
1/13/2023	P	5443 47 Ave S	Insurance Agent	767	AE - 905.7	-2.3	MI 1-4	N	Y	Looking for LOMR or EC. Built in 2011, none on file
1/17/2023	P	3121 Timberline Cir S	Frank	777	X - N/A	N/A	MI 1-5	N	Y	Question about flood zone, no insurance required
1/17/2023	P	2349 58 Ave S	Audrey	787	AE - 907.2	0.2	MI 1-4	N	Y	Verifying building is in floodplain
2/7/2023	E	4969 37 Ave S	Adam - GCB	778	AE - 905.7	-1.3	MI 1-6	N	Y	LOMR question on replatted lot
2/28/2023	E	3243 37 Ave S	Steve Strege	779	AE - 905.5	-0.5	MI 1-6	N	N	Water elevation vs. river stage question
3/13/2023	O	6251 13 Cir S	Aaron Nissen	791	AE - 907.5	-0.5	MI 1-6	N	Y	Looking to see if prop LOMR out. If not recommend EC and LOMA if applicable
3/21/2023	P	7450 Claire Dr S	Owner	795	AE - 908.5	0.5	MI 1-6	N	Y	Flood risk & insurance questions
3/28/2023	P	Multiple	Nancy Gustafson	Multiple	Multiple	N/A	MI 1-6	N	Y	3698 Fairway Rd N, 806 Oak St N, Maple Valley Addn: Areas in SFHA; Veteran's Park Addition not in SFHA
4/4/2023	P	1657 62 AVE S	Steven Cole	791	AE - 907.5	-0.5	MI 1-4	N	Y	Property is above 907.5 BFE/42.5 flood stage
4/27/2023	P	2043 Rose Creek Blvd S	Kristie Kelsch	787	AE - 905.7	-2.3	MI 1-4	N	N	Inquiring on house 1st floor elevation
4/28/2023	P	6425 15 St S	Kari Fischer	791	AE - 908	-2	MI 1-4	N	N	Inquiring on house 1st floor elevation
7/10/2023	E	4104 52 St S	Lexi Hoffman	778	AE - 905.7	-1.3	MI 1-4	N	Y	How to apply for LOMA
7/10/2023	PIE	5037 44 St S	Peggy	786	AE - 905.7	-1.3	MI 1-4	N	Y	Looking for EC for LOMA
7/11/2023	P	6267 16 St S	Colette Erickson	791	X - N/A	N/A	MI 1-6	N	Y	Recommended insurance but not required
9/12/2023	P	1107 37 Ave S	Sid Liem	783	AE - 905.4	-0.4	MI 1-4	N	Y	For sale by owner home
10/20/2023	P	5225 18 St S	Alicia	791	AE - 906.8	0.8	MI 1-6	N	Y	Confirming flood insurance required
10/23/2023	P	7102 12 St S	Todd Kiser	795	AE - 908.3	0.3	MI 1-4	N	Y	Regulations for future outbuildings
12/13/2023	P	3308 Adams St S	Meredith Canchini	778	AE - 905.7	0.7	MI 1-4	N	Y	Sent LOMA
1/2/2024	P	3883 50 St S	Maureen Bartelt	778	X - N/A	N/A	MI 1-7	N	Y	Realtor asking about floodplain in drain



MCM 4 – Construction Site Program

The construction program's goal is to reduce pollutant discharge due to construction/development activity. Our program is administered principally by the Fargo Storm Sewer Utility Department (SSU) under the authority of the Fargo City Engineer and the Stormwater Ordinance. The Engineering Department contributes significantly to the program with site plan review for both public and private commercial development and has overall responsibility for public sector construction.

Below is a description of the program's basic functions and methods of operation. Located at the end of this section are support documentation examples, evaluation and future consideration.

ESC Permitting System

All new building sites and land disturbing activities that have a potential to discharge sediment off a site are automatically issued an **Erosion and Sediment Control Permit** (ESC Permit) (37.0301). This process now begins at the inspections department when applying for a building permit. The purpose of the permit is to provide site identification, point of contact information and a formal record. The official "tracking" system (LAMA) is maintained daily by SSU staff. This system has archive capability with a search-by address/document number function; it covers both commercial and residential construction sites.

ESC Permit

Commercial permitted sites must also undergo the engineering department's site plan review process which contains a stormwater review element.



Builders of one and two unit residential buildings are permitted but subscribe to the department's **Stormwater Guide** versus site plan submittal for commercial sites (37.0102). These construction sites are patrolled on a regular basis as determined by the stormwater inspector for site conforming conditions. Discrepancy observation can be resolved with personnel on site or through the notice of violation procedure. (See patrol & enforcement)

Site plan review (submittal) “One and two unit residential buildings are exempt”

A construction site plan is required for development under Chapter 37. The ESC Permit application requires operators of commercial sites to submit a site plan (SWPPP) with all related BMPs and water quality & retention addressed including type and location on the site. The site plan review requirement is part of the Land Development Code (LDC) and includes identification of permanent stormwater BMPs. Engineering evaluates all infrastructure connections and conflicting site conditions. Non-conforming scenarios are notated and the plans must be returned for correction. This site plan review ensures compliance with the LDC, stormwater requirements of the North Dakota Department of Environmental Quality NDPDES construction permit (NDR11-0000), MS4 discharge permits and the City of Fargo Stormwater Ordinance.

Additionally, SSU staff reviews plan sheets prior to issuance of an ESC Permit. This review concentrates on the plan’s **temporary physical placement** of BMPs including:

- **Conforming inlet protection**
- **Dewatering**
- **Perimeter control**
- **Stockpile locations**
- **Tracking management (egress/ingress)**
- **Unique BMP proposals**
- **Concrete and similar washout treatments (grindings and mortar)**

Commercial Compliance Inspection

Commercial sites undergo a SSU staff evaluation (on an annual or complaint basis) once construction gets underway. Here the inspector compares the plan with the site condition and converses with the superintendent about any particular nuances associated with the site. The discussion also elaborates the need to document BMP site changes on the SWPPP.

Patrol and Enforcement

SSU staff uses the permit system for permit verification, developing compliance patrol routes and overall enforcement composition. Construction sites, patrolled on a rotating daily basis may be addressed via personal interaction with a site operator, phone call or issuance of a Notice of Violation (NOV)/Order to Correct. Infractions have a 48-hour correction period with the exception of a live discharge, which requires immediate response. Each site must conform to the criteria of the Stormwater Ordinance for construction site **condition/pollutants**: (refer to the statistical section of this MCM for annual and historical data).

- **BMPs**
- **ESC Permit**
- **Entrance**
- **Grass buffer**
- **Inlet protection**
- **Illegal Discharge (Illicit)**
- **Street tracking**
- **Other**

The screenshot shows a digital form titled "Notice of Stormwater Violation" from the City of Fargo Engineering Department. The form is designed for reporting and documenting violations at construction sites. It includes several key sections: a header with the city logo and department information; a "Confirm Receipt Immediately" section with a "Print" button; a "Site Deficiency Statements" section with a list of checkboxes for various violations; a "Comments/Action Required" text area; and a bottom section for "Inspector/Officer" and "Site Operator" with checkboxes for "Escorted" and "Not Escorted". The form also includes a "TOTAL" field and a "Print" button.

Citizen Contact, Complaints and Contributions Log

Public contact is logged at several interface portals including: Fargo One, City Email Accounts, Facebook and Twitter which are each directed to appropriate departments. The digital media has its own historical tracking element and SSU maintains records in the department database. Public input is evaluated and topics of merit are communicated back to the site operator via comment or official infraction notice.

Written Procedures

The SSU department has established written procedures for site inspections, issuance of Notice of Violation (enforcement), site plan review and response to public input. Please refer to the supporting documentation at the end of this segment.

Stabilization Requirements

The requirement for construction stabilization is established by definition in the Stormwater Ordinance. Examples of the stabilization requirement are cited below. Please refer to the actual ordinance for more information.

- "**Temporary protection**" means short-term methods employed to prevent erosion. Examples of such protection are straw, mulch, erosion control blankets, wood chips, and erosion netting. 37.10203.50
- "**Stabilize**" means the exposed ground surface has been covered by appropriate materials such as mulch, staked sod, riprap, wood fiber blanket, or other material that prevents erosion from occurring. Grass seeding alone is not stabilization. 37.0102.39
- "**Stabilized**" means the exposed ground surface after it has been covered by sod, erosion control blanket, riprap, pavement or other material that prevents erosion. Simply sowing grass seed is not considered stabilization. Ground surfaces may be temporarily or permanently stabilized (also see Final Stabilization).
- "**Erosion control**" means methods employed to prevent erosion. Examples include soil stabilization practices, horizontal slope grading, temporary or permanent cover, and construction phasing.
- "**Sediment control**" means the methods employed to prevent sediment from leaving the development site. Examples of sediment control practices include, but are not limited to silt fences, sediment traps, earth dikes, drainage swales, check dams, sub-surface drains, pipe slope drains, storm drain inlet protection and temporary or permanent sediment basins. 37.0102.37
- "**Final stabilization**" means that disturbing activities at the site have been completed and a uniform perennial vegetative cover with a density of 70 percent of the native cover for unimproved areas and areas not covered by permanent structures, or equivalent permanent stabilization measures (such as the use of riprap, gabions, or geotextiles) have been employed. 37.10203.40

CONSTRUCTION INDUSTRY EDUCATION AND INFORMATION

The City of Fargo Stormwater Program partners with Fargo-Moorhead Homebuilders Association to develop rules, policy guidance and training. The association is comprised of commercial/residential builders, material, service suppliers and related businesses (developers, realtors, etc.) SSU staff regularly contributes to the partnership with newsletter articles, presentations or submissions of new technology.

SSU also communicates directly with contractors via digital **email** links. Reminders, requirements and changes are communicated to an ever-changing roster of contractors. Email lists are compiled from the permit contact database to ensure effective information dissemination.

Fact sheets are used to convey stormwater messaging to ancillary business such as lawn care, delivery firms, etc. The information presented may be specific or broad based, depending on the target audience.

Finally, staff conducts **specialty education presentations** upon request. Including preparatory and secondary classroom lectures, PowerPoint presentation and informational outreach.

See all the construction education related programming under MCM 1 & 2.

Cooperating Partners

The program also works via a cooperative agreement with NDSU (another MS4) for their construction erosion and sediment control permitting and enforcement programming. SSU staff verifies necessary permitting and enforces the same stormwater regulations on campus and throughout the entire city. Public Works monitors interface connections and maintenance issues between the two systems.



Statistical Data

A statistical dataset is maintained on the construction program. This report provides annual and previous years' data for trend analysis and program performance. A current copy of the report is included at the end of this segment.

MCM 4 Future Goals

In March of 2022 SSU Staff partnered with the Fargo-Moorhead Homebuilders Association, NASECA, and the North Dakota DEQ providing a conference to educate local homebuilders and contractors on construction site runoff. The goal in 2024 is to continue to attract more interest from the private sector for this as an annual event in an effort to educate local builders and contractors right around the startup of a new construction season.

Fargo's NPDES construction site pollution control program (MCM 4) addresses potential pollution discharging from a construction or disturbed land site and has been in existence since 2006. The program concentrates on discharges due to water runoff, wind or vehicle tracking. Sediment, garbage, washout areas, dewatering, stockpiles and access are controlled. This year's annual report provides feedback on the effectiveness of our control measures.

PERMITS

In 2023 permits decreased slightly. Storm Sewer Utility Staff still conducted routine weekly inspections of construction sites with the number of vehicle track out infractions citywide. Many infractions are also addressed by phone for efficiency. BMPs still remain the largest infraction - see the violations section.

The Lama permitting system was implemented in 2019. The software creates a smooth process of tracking construction activity throughout the city. This system triggers an Erosion & Sediment Control permit at the inspections department during the approval process for a building permit. The system is still evolving as we learn more tips and tools but allows SSU personel to track and manage our construction site runoff program with ease.

Revenue generated from permit and associated fees remains but a small percentage of the program's total operating cost.

Permits	Issued	\$ Revenue	Violations	\$ Fees	Violations to Permits	Specific Infraction	Inspectors	\$ Total Revenue
2023	332	\$6,640	73	\$0	22%	107	KJM/PLA	\$6,640
2022	380	\$7,600	138	\$360	36%	206	KJM/ADZ	\$7,960
2021	385	\$7,700	159	\$120	41%	203	KJM/WJM	\$7,820
2020	403	\$8,060	126	\$120	31%	181	KJM	\$8,180
2019	305	\$6,100	266	\$1,140	87%	337	KJM/SO	\$7,240
2018	389	\$8,894	246	\$1,140	63%	323	KJM/DN	\$10,034
2017	424	\$9,345	263	\$840	62%	313	KJM/BN	\$10,185
2016	510	\$11,717	278	\$540	55%	367	KJM/JCL	\$12,257
2015	496	\$11,282	478	\$2,640	96%	691	JP/TS/KM	\$13,922
2014	434	\$10,162	428	\$3,240	99%	765	Josh P	\$13,402
2013	585	\$13,393	243	\$1,740	42%	455	Josh P	\$15,133
2012	458	\$11,648	307	\$1,740	67%	563	Josh P	\$13,388
2011	395	\$8,936	190	\$572	48%	408	Josh/Mark	\$9,508
2010	362	\$7,917	229	\$390	63%	463	Joe	\$8,307
2009	362	\$7,496	295	\$300	81%	477	Craig	\$7,796
2008	428	\$10,785	304	\$3,240	71%	575	Mike	\$14,025
2007	489	\$11,636	331	\$2,880	68%	1,166	John	\$14,516
2006	367	\$7,460	36	-	10%	36	Steve	\$7,460
2005	0	\$0	0	-	0	0	0	-

Violations

Violations during 2023 remained consistent although Storm Sewer Utility staff changed mid season. Due to this change in staffing commercial site inspections were down slightly for the year. All active permitted sites throughout the construction season will be inspected in the 2024 Season. BMP as an infraction annually tops the list of infractions because it is a more ambiguous (catch-all) term. All infractions not specifically denoted independently are grouped into BMP.

There are several facets to the tracking issue including material delivery, staff (parking & tool off-load), construction equipment, etc. Compounding these elements is the ever shrinking lot sizes which muddles traditional construction practices (maneuverability).

Year	NOVs Issued	Grass BMP	Illegal Buffer	Illegal Entrance	Illegal Discharge	Inlet Protection	Permit	Tracking	Total
2023	73	30	2	4	1	18	0	32	87
2022	138	80	2	35	5	19	0	65	206
2021	159	89	2	25	6	10	0	65	197
2020	126	82	6	30	1	4	0	51	181
2019	266	213	10	47	2	17	9	34	337
2018	246	84	4	77	3	35	35	68	323
2017	263	131	32	19	4	20	19	83	313
2016	278	124	6	47	4	23	13	120	367
2015	478	330	2	62	2	27	47	175	691
2014	428	233	2	67	4	74	37	188	765
2013	243	123	24	76	14	22	67	71	455
2012	307	155	14	155	7	34	119	50	563
2011	190	110	11	51	2	32	44	125	408
2010	229	175	18	66	3	35	56	76	463
2009	295	175	16	93	2	43	38	64	477
2008	304	197	8	130	16	34	44	121	575
2007	351	291	152	340	8	38	178	65	1166
2006	36	-	-	-	-	-	-	-	36
2005	-	-	-	-	-	-	-	-	-

Profiling

Contractor	Permits	Violations	Leading Infractions	% Violations To Permit
Jordahl Custom Homes	114	25		21.9%
Thomsen Homes	65	28	BMP maintenance	43.1%
Dabbert Custom Homes	36	2	Street Tracking	5.6%
Brookstone Properties	15	12	Illegal Entrance	80.0%
Adams Development	9	1		11.1%
Designer Homes	8	5		62.5%
Heritage Homes	7	0		0.0%
Krueger Construction	7	2		28.6%
Eid-Co Buildings, Inc	6	3		50.0%
	267	78		
Top 9 permit holders account for	70% of permits and 57% of all violations			

HOMEBUILDER GUIDELINES

FOR EROSION AND SEDIMENT CONTROL

Sites Disturbing Less Than One Acre

Homebuilders must reduce soil loss during home construction. This fact sheet provides general erosion and sediment control (ESC) and stabilization guidelines for homebuilding and other construction that disturb less than one acre.

Each site is different. Some lots can require additional or alternative controls. Check with local officials to make sure all ESC requirements are addressed. ESC devices must handle a two-year, 24-hour rain event. A two-year, 24-hour event ranges from 1.9 inches of rain in western North Dakota to 2.3 inches of rain in the eastern part of the state over a 24-hour period.

PERIMETER CONTROLS

Perimeter controls capture soil before it leaves the construction site. These types of controls include vegetative buffers, silt fences and fiber rolls.

Vegetative buffers consist of a strip of dense grass. One foot in buffer is used for every five feet of disturbed area that drains to it.

Silt fence and fiber rolls are examples of controls used to capture sediment. Controls of this type capture sediment by ponding water behind them. Ponding allows soil to settle out of the water. A rule of thumb for silt fence is to use a one linear foot of silt fence for every 100 square feet of unslope disturbed area.

ROOF DRAINS

Roof drains need to be provided with adequate splash pads and/or downspouts extensions to prevent erosion from roof runoff.

INLET PROTECTION

Inlet protection devices keep soil out of the storm sewer system. They are a last line of control and must be used with other ESC and stabilization methods. Inlet protection devices need to be selected and installed so water can bypass the device if flooding is a concern.

STABILIZED SITE EXIT

A stabilized construction site exit reduces dirt tracked from the site. Vehicles and equipment must not exit the site from any other place, especially when wet soil conditions are present.



INSPECTIONS & HOUSEKEEPING

Inspect ESC devices every 14 calendar days and within 24 hours of 1/4 - inch rainfall.

Maintenance or repair should be completed following good housekeeping practices, which includes cleaning and maintain ESC devices, cleaning dirt off streets and picking up debris.

Clean sediment control devices such as silt fence, before sediment has reached half of the exposed height. Repair or replace the device if it is not functioning properly. Removal of sediment or device if it is not functioning properly. Removal of sediment or device repair/replacement needs to be done within 24 hours of discovery or as soon as field conditions allow.

Clean out sediment traps and basins when the storage volume is reduced by half. This must be done with 72 hours or as soon as field conditions allow.

Remove dirt from streets by the end of the work day.

ESC and stabilization must be maintained at the site until there is 70 percent vegetative cover or the site is turned over to the homeowner.

TEMPORARY & PERMANENT COVER

Temporary cover is used to reduce erosion and should be applied to areas where construction activity has ceased and is not planned to resume for 14 days. Temporary soil stockpiles such as clean aggregate, demolished concrete and sand stockpiles are exempt. Temporary cover may be obtained by planting, mulching or using an erosion control blanket.

Permanent cover is any type of cover that will not be disturbed again by construction activities.

MATERIAL STORAGE

Stockpiled material cannot be placed in any stormwater conveyance system (e.g., curb and gutter, drainage ditch).

Sediment controls need to be placed between any stockpile and stormwater conveyance system. Stockpiled material should not be placed directly against any device.

Liquid or soluble materials (e.g., oil and paint) must be stored to prevent spills or leaks.

WASTE DISPOSAL

All construction debris must be placed in an appropriate container to prevent it from being carried away by wind or water. Dispose of all debris at any appropriate facility.

CONCRETE WASH WATER

Concrete wash water cannot be placed in or allowed to drain to any surface or groundwater or storm sewer system. Place concrete wash water in an appropriate collection system.

Source: North Dakota Department of Environmental Quality

MCM 5
Post Construction Program



- **MCM 5 – Post-Construction Stormwater Management**

The City of Fargo has developed, implemented, and enforces a post-construction pollution reduction program for new and redevelopment projects within its jurisdiction. This includes projects that disturb one or more acres and smaller projects that are part of a larger common plan of development. These “specific requirements” meet or exceed state mandated levels outlined in Appendix 1 of the North Dakota MS4 Permit - NDR04.

Chapter 37 Stormwater Management (regulatory method)

The Stormwater Ordinance establishes criteria for the post-construction stormwater program. Our program sets specific control requirements for the runoff rate and water quality treatment per site, for all development projects including those less than one acre.

Program Outline

- Storm Policy sets specific stormwater guidelines and has computation tables
- Construction/development applications must submit site plans for review/approval with stormwater features: locations, volume and runoff calculations, BMP and maintenance issues.
- Projects areas are evaluated on a per site basis under the site plan review process (see below).
- All previously undeveloped properties and subdivisions are required to provide a Storm Water Management Plan (plan) for the subject area.
- Submission and approval of the plan is required prior to plat approval.
- Failure to comply with the requirements of a site plan review results in a no build situation.

Site Plan Review Process

During the site plan review process, (a requirement set forth in the Land Development Code (LDC)) engineering evaluates all infrastructure connections and conflicting site conditions, including permanent stormwater BMPs. Non-conforming scenarios are notated and the plan returned for correction. This site plan review ensures compliance with the LDC, stormwater requirements of the North Dakota Department of Environmental Quality NDPDES construction permit (NDR11-0000) and MS4 discharge permits and the City of Fargo Stormwater Ordinance.

This process verifies the post construction aspect for permanent stormwater treatment. Each site plan submittal is reviewed via a check-off list for conforming release rates, detention volumes, pipe sizing, etc. Permanent detention features allow options to applicants regarding detention by providing large-scale (regional) retention. A Stormwater Management Report prepared by a Professional Engineer registered in the state of North Dakota, indicating compliance with the discharge rate is required for all developments. Detention/retention volume requirements will be established by the discharge limitation.

GENERAL STORMWATER REQUIREMENTS

Authority and Purpose

The City of Fargo operates a Municipal Separate Storm Sewer System (MS4) under authority of the North Dakota Department of Environmental Quality Permit NDR04-0000 (Discharge Permit), and City of Fargo Code of Ordinances, Chapters 17 and 37. In compliance with this authority, Fargo has developed this Policy on Stormwater Discharge and Treatment Requirements. This policy establishes standards for stormwater discharge rates and stormwater quality treatment for all development within the City of Fargo's jurisdiction.

Intent of the Policy

The intent of this policy is to provide guidance to those persons working with the City of Fargo **Stormwater Management Ordinance** and to establish uniform, simplified standards that work within the framework of the City's storm sewer infrastructure.

Target Audience

This policy is applicable to all development (Code of Ordinances, Chapter 37, Paragraph 37-0102 7.) under the jurisdiction of the City of Fargo.

Stormwater Management Plan

All previously undeveloped properties and subdivisions; re-plats of existing properties for purposes of development; or re-development of existing developed or un-developed lots one (1) acre in size or larger, or part of a larger common development that is one (1) acre in size or larger, shall provide a Stormwater Management Plan (plan) for the subject area.

Submission of a schematic stormwater management plan shall be included with submittal of the draft plat for approval. Submission and approval of the full stormwater management plan is required prior to construction plan approval. Stormwater management plan requirements are discussed in **Appendix A**.

Existing Parking Lot Stormwater Requirements

Stormwater management requirements for existing parking lots are outlined in **Appendix B**.

Stormwater Discharge Requirement/Limit

The maximum stormwater discharge rate as defined in **Appendix C** or **Appendix D** shall apply to the following categories:

1. Newly Platted Ag Conversion that is (1) one acre in size or larger or is part of a common development one acre in size or larger (**Appendix C**).
2. Re-plat of currently platted parcel that is part of a common development that is one acre in size or larger and is currently undeveloped (**Appendix C**).
3. Re-development of existing parcel that is one acre in size or larger, or is part of a common development that is one acre in size or larger (**Appendix D**).

Water Quality Treatment

Water quality treatment is required for all new developments or re-plats one (1) acre in size or larger, common developments collectively one acre or larger, re-development sites one acre or larger, and on existing parking lots as outlined in **Appendix B**. Requirements for water quality treatment are specified in **Appendix E**.

Stormwater Detention, Retention, and Discharge Pond Design

Appendix F outlines the requirements for stormwater pond design.

Design Requirements within Special Zones

Appendix G covers the design parameters and coverage area for special design requirement areas, including areas that have been developed with regional drainage facilities, and the Downtown Mixed Use zoning area.

APPENDIX A

STORMWATER MANAGEMENT PLAN

1. The Stormwater Management Plan schematic preliminary drawing and final plan shall be prepared by a Professional Engineer registered in the State of North Dakota.
2. All newly platted Ag Conversion properties, new subdivisions within a larger common development, and infill projects within a larger platted development equal to or greater than 1 acre in size are required to have a stormwater management plan that includes those Best Management Practices (BMPs) required for the addition or subdivision to meet stormwater quality and quantity requirements. Approval of the regional stormwater management plan is considered part of the plat approval process.
3. Previously platted lots less than one acre in size, which are part of a larger common development, will be required to have a stormwater management plan when the lot is developed. This stormwater management plan shall analyze the impact this newly improved lot will have on the overall stormwater features of the common development. As a minimum, these lots shall drain to a common inlet that is connected to the City storm sewer system, while meeting the allowable release rate and water quality requirements.
4. Article 37-0201 of the City of Fargo Code of Ordinances states: “An owner must submit to the City Engineer a plan for stormwater management and control including detention and retention facilities. The plan shall be submitted, and approval obtained from the City Engineer prior to the owner (a) obtaining approval of an application for a plat, pursuant to Section 20-0907 of the Land Development Code of the City, or (b) engaging in any land disturbing activity.”

The plan may include “in the discretion of the City Engineer, arrangements for further planning and implementation of permanent facilities for stormwater management and control by subsequent owners of the property being platted or by the current owner at a later time.” Delay in producing the stormwater plan will be considered when extenuating circumstances dictate but will generally not be allowed.

5. The stormwater management plan, at a minimum, shall consist of:
 - a) A Stormwater Management Plan Report prepared using a stormwater modeling system that provides a modeling report similar in nature to HydroCad. The report shall document the assumptions, methodologies, and analysis used in arriving at the selected stormwater management solution. The report must be global, in that it looks at the entire area to be developed as well as any impacts to the site created by neighboring areas. The report shall be conceptual in nature and include:

1. A narrative describing the existing site conditions, proposed site conditions, types and locations of stormwater BMPs proposed to be used.
 2. Model calculations for the post-development 2-, 10-, and 100-year storm events as identified under the most current NOAA Atlas precipitation data for Fargo.
 3. Hydrographs depicting flows into and out of all detention/retention facilities and all flows into the City storm sewer system.
- b) Conceptual plan drawings and topographic maps noting all items covered in the report.
1. A detailed drawing of the outlet structure indicating maximum water elevations for the 2-, 10-, and 100-year storms.
 2. A written description of the proposed water quality treatment method.
- c) Conceptual Operations and Maintenance (O&M) plan for the system, covering all requirements for keeping the system operating as designed.

The above-noted items shall be stamped and signed by a Professional Engineer registered in the State of North Dakota.

6. The plan may utilize regional or on-site detention/retention and water quality facilities; however, per the Fargo Comprehensive Plan, the City prefers to see stormwater facilities constructed as regional amenities whenever possible. A regional stormwater plan can use any combinations of BMPs, selected by the owner and their engineer, which enable the benefitting properties to meet the stormwater quantity and quality requirements. If a regional facility is used, the pond shall be located to facilitate capture of as much site stormwater as possible prior to discharging into the City stormwater system.
7. The submitted conceptual stormwater plan will be reviewed by the City's Engineering Department. The Engineering Department will evaluate the stormwater plan and communicate change requirements or recommendations to the owner and their engineer. Changes made to the stormwater plan prior to plat approval will be considered part of the original plan. If the plan is very complex, it may be brought before the City Commission for discussion and/or public comment prior to approval.
8. If a subdivided property is covered by a previously approved stormwater plan, the previously approved plan shall be reviewed to determine if the subdivided property is still in compliance. A letter from a North Dakota Registered Professional Engineer can accomplish this with City Engineer review and approval.

9. The approved plan will exist for the life of the subject property, including any changes approved by the City Engineering Department. The final approved plan will be included with the amenities plan.
10. The plan may require dedication of stormwater or access easements or additional right-of-way for the construction of stormwater conveyance and/or storage facilities.
11. The plan must ensure the subject area conforms to the site specific performance requirements noted in **Appendices B, C, D, and E** of this policy.

APPENDIX B

EXISTING PARKING LOT STORMWATER REQUIREMENTS

Current parking lots being maintained, repaired, replaced, or expanded shall comply with the requirements outlined in this Appendix and shall follow the following categories.

1. Application of these requirements and whether or not City storm sewer is available within a reasonable distance of the site shall be as determined by the City Engineer.
2. Parking lots that expand over time beyond the original grandfathered project may add enough impervious surface through surfacing or added buildings to trigger stormwater requirements.
3. Existing Parking Lot maintenance or repairs, including up to complete removal of asphalt or concrete surfacing, localized repair of gravel or subgrade, or surface treatments (spray coatings, chip/fog seals, crack sealing, striping), with no expansion of the current parking areas and result in no change in drainage, will be exempt from the stormwater requirements.
4. For existing parking lots that are (1) one acre to under (3) three acres and that involve full asphalt or concrete removal, or extensive gravel and subgrade modifications, or mill and overlays that result in modification of drainage patterns, the site shall be required to collect on-site stormwater into inlets, add a water quality device, and convey stormwater into the City stormwater system. A pre-versus post-development drainage study shall be done. If the post-construction flows are the same or less than the pre-construction flows, then no detention is required. If the post-construction flows are larger, then detention shall be required to mitigate the increase in flow only.
5. Existing parking lots (3) three acres or larger that involve full parking lot reconstruction (to include full pavement & base removal) shall be required to collect on-site stormwater in inlets and convey stormwater into the City storm sewer system, and shall comply with stormwater requirements contained in **Appendices C/D and E** for modeling, discharge rate control, and water quality for the existing parking lot being reconstructed and improved.
6. A pre-post stormwater model shall be accomplished for any site, one acre or larger, on which a building addition/expansion is triggering expansion of the parking lot(s). If the post-construction model results in a greater stormwater discharge rate than the pre-construction model during the 100-year event, discharge rate of the added volume shall meet City discharge rate requirements. If the new impervious area is over one acre, water quality requirements must also be met.

APPENDIX C

STORMWATER DISCHARGE REQUIREMENTS (NEWLY PLATTED DEVELOPMENT OR UNDEVELOPED EXISTING PLATS)

1. The discharge rate for stormwater discharging from any site, equal to or greater than 3 acres in size, into any drain system within City jurisdiction, shall be limited to 1 cfs/acre. For parcels between 1 and 3 acres, the maximum discharge shall be per the following table:

Parcel Size (Acres)	Release Rate (cfs)
1.0	2.00
1.1	2.05
1.2	2.10
1.3	2.15
1.4	2.20
1.5	2.25
1.6	2.30
1.7	2.35
1.8	2.40
1.9	2.45
2.0	2.50
2.1	2.55
2.2	2.60
2.3	2.65
2.4	2.70
2.5	2.75
2.6	2.80
2.7	2.85
2.8	2.90
2.9	2.95
3.0	3.00

This table shall apply to all projects covered under this policy except existing parking lots, which are addressed in **Appendix B**, and re-development of currently developed properties, which are addressed in **Appendix D**.

2. A stormwater report is required for all developments one acre in size or greater or if part of a larger common development that is one acre or larger. The report must comply with the requirements specified in **Appendix A**.
3. All sites except existing parking lots (as described in **Appendix B**) are required to comply with the State Water Quality Design Considerations. Water Quality Design Consideration information is included as **Appendix E** to this policy.
4. The discharge rate noted above will drive detention requirements for a particular site. Dry or wet ponds, oversized pipe, underground stormwater storage facilities, or other methods can be used to achieve required storage volumes.

If a regional detention system, as opposed to site-specific ponds, is chosen for the development area, all water shall be routed to the regional pond prior to discharge into the City system. The original, conceptual stormwater plan (see **Appendix A**) must address the conveyance of stormwater from all parcels in the development to the regional detention facility and shall cover all details of operation and maintenance responsibilities.

If the City of Fargo storm sewer system provides conveyance to the regional facility, the 1 cfs/acre criteria shall be used unless otherwise planned for. If the owner requires larger flows to the regional facility, this must be considered/negotiated during the development of the original regional stormwater plan and the original amenities plan (such as parallel storm sewer lines or open channel flow to existing ponds).

5. Discharge or overland flow of stormwater onto a neighboring property shall not be allowed unless included in the regional plan (see **Appendix A**) and facilitated through the designation of required easements, dedications, or other methods allowing such conveyance.
6. The State of North Dakota Water Quality standards must be met. The method of treatment shall be selected by the design engineer from the options presented in **Appendix E** or as approved by the City Engineer.

Construction of rain gardens, grassy swales, and other methods of achieving water quality are encouraged and will be evaluated on a case-by-case basis.

7. Criteria for construction of regional detention facilities is discussed in **Appendix F**.
8. Each plan set submittal requiring retention/detention shall include a storm system table identifying:
 - Lot size (acreage and square feet)
 - % impervious area

- Required retention/detention volume (100-year storm event)
- Supplied retention/detention volume (100-year storm event)
- Water quality method being proposed, including manufacturer's data
- Allowable release rate for 100-year event (cfs)
- Actual release rate for 100-year event (cfs)

APPENDIX D

RE-DEVELOPMENT OF CURRENTLY DEVELOPED PROPERTIES

- For re-development of currently developed properties, Fargo has increased the allowable release rates to take into account expected existing impervious areas. It should be noted that increases in the release rates for 1 to 4 acre sites is greater than the rate increases for 4 to 8 acres. Fargo believes that re-developments of 4 to 8 acres have more latitude to accommodate stormwater runoff mitigation within the design. The stormwater discharge rate from any site, equal to or greater than 8 acres in size, into any drain system within City jurisdiction, shall be limited to 1 cfs/acre. For parcels between 1 and 8 acres, the maximum discharge shall be per the following table:

Parcel Size (acres)	Allowable Release Rate (cfs)
1	3
1.5	3.77
2	4.53
2.5	5.3
3	6.07
3.5	6.83
4	7.6
4.25	7.64
4.5	7.68
4.75	7.72
5	7.76
5.25	7.79
5.5	7.82
5.75	7.85
6	7.88
6.25	7.9
6.5	7.92
6.75	7.94
0.7	7.96
7.25	7.97
7.5	7.98
7.75	7.99
8	8

This table shall apply to all projects covered under this policy except existing parking lots, which are addressed in **Appendix B**, and newly platted development or existing undeveloped plats, which are addressed in **Appendix C**.

In no circumstance shall the allowable release rate from a re-development lot be greater than the pre-redevelopment release rate. The current condition of the lot shall be evaluated up to 5 years prior to re-development to determine existing impervious values for determining acceptable release rates.

2. A stormwater report is required for all developments one acre in size or greater or if part of a larger common development that is one acre or larger. The report must comply with the requirements specified in **Appendix A**.
3. All sites except existing parking lots (as described in **Appendix B**) are required to comply with the State Water Quality Design Considerations. Water Quality Design Consideration information is included as **Appendix E** to this policy.
4. The discharge rate noted above will drive detention requirements for a particular site. Dry or wet ponds, oversized pipe, underground stormwater storage facilities, or other methods can be used to achieve required storage volumes.

If a regional detention system, as opposed to site-specific ponds, is chosen for the development area, all water shall be routed to the regional pond prior to discharge into the City system. The original, conceptual stormwater plan (see **Appendix A**) must address the conveyance of stormwater from all parcels in the development to the regional detention facility and shall cover all details of operation and maintenance responsibilities.

If the City of Fargo storm sewer system provides conveyance to the regional facility, the 1 cfs/acre criteria shall be used unless otherwise planned for. If the owner requires larger flows to the regional facility, this must be considered/negotiated during the development of the original regional stormwater plan and the original amenities plan (such as parallel storm sewer lines or open channel flow to existing ponds).

5. Discharge or overland flow of stormwater onto a neighboring property shall not be allowed unless included in the regional plan (see **Appendix A**) and facilitated through the designation of required easements, dedications, or other methods allowing such conveyance.
6. The State of North Dakota Water Quality standards must be met. The method of treatment shall be selected by the design engineer from the options presented in **Appendix E** or as approved by the City Engineer.

Construction of rain gardens, grassy swales, and other methods of achieving water quality are encouraged and will be evaluated on a case-by-case basis.

7. Criteria for construction of regional detention facilities is discussed in **Appendix F**.
8. Each plan set submittal requiring retention/detention shall include a storm system table identifying:
 - Lot size (acreage and square feet)
 - % impervious area
 - Required retention/detention volume (100-year storm event)
 - Supplied retention/detention volume (100-year storm event)
 - Water quality method being proposed, including manufacturers' data
 - Allowable release rate for 100-year event (cfs)
 - Actual release rate for 100-year event (cfs)

APPENDIX E

MS4 WATER QUALITY DESIGN REQUIREMENTS

The following information is taken from page 29 of the current North Dakota NDR04-0000 MS4 Permit, dated April 1, 2021 and effective to March 31, 2026.

Water Quality

A water quality treatment system is required in developments as defined under **Appendices B, C, & D**. The system must meet the minimum standards specified below.

The post-construction controls outlined below are intended to manage water quality by reducing pollutants carried in the first flush of stormwater runoff.

The design considerations for treating a water quality volume for common post-construction controls are as follows:

Control	Water Quality Design Consideration
Wet Detention Ponds	Water Quality Volume (V_{wq}) = 1800 ft³ per impervious acre draining to the pond. The drawdown time for the V_{wq} should be a minimum of 12 hours.
Dry Detention Ponds (w/Extended Detention)	Extended Detention / Water Quality Volume (V_{wqed}) = 1800 ft³ per impervious acre draining to pond. The drawdown time for the V_{wqed} should be a minimum of 24 hours and not more than 72 hours.
Infiltration	Water Quality Volume (V_{wq}) = 0.5 inches from impervious area. The volume captured in rain gardens, or passed through bio filters with under drains, would be grouped with infiltration for water quality treatment.
Flow-Through Treatment Devices	Size devices to treat the first 0.5 inches of runoff from impervious area.
Redevelopment / Retrofit	Incorporate water quality criteria by reducing impervious surface area and implementing controls to treat the first 0.5 inches of runoff from impervious areas.

The water quality criteria apply to on-site or regional systems for post-construction stormwater management. The water quality considerations do not replace or substitute for water quantity or floodplain management requirements for development. The water quality features may be incorporated into the design of structures for flow control or water quality control may be achieved with separate features. Flow-through treatment devices

such as “Defenders™” shall provide a minimum of 80 percent removal of sediment with a particle size distribution equivalent to the standard OK-110 at a feed concentration of 300 mg/L. The treatment device design shall include a bypass for storm flows above the ½” rain event from the impervious area being served.

If it is impractical to meet the water quality criteria, alternative practices may be used (e.g., grassed swales, smaller ponds, or grit chambers). If a combination of practices is used, the water quality volume is accounted for on a percentage basis. Low impact development and/or green infrastructure practices may be used as an alternative to post-construction controls.

The selection and design of post-construction controls must consider clogging or obstructions, freeze-thaw cycles, effects on slope stability and groundwater, and the ability to effectively maintain the control. Design post-construction controls for ease of inspection and maintenance access (e.g., a stabilized access that allows equipment to enter a pond).

Recommended resources for planning and designing controls for urban stormwater runoff are found in the “North Dakota Stormwater Criteria Manual”: <https://www.dot.nd.gov/manuals/design/designmanual/designmanual.htm>

The property owner is responsible for operating and maintaining the water quality device in accordance with the manufacturer’s recommendations. The property owner shall maintain records of maintenance of the water quality device and shall prepare an annual inspection report. These records are to be maintained with the property owner and shall be made available to the City upon request.

APPENDIX F

STORMWATER DETENTION, RETENTION, AND DISCHARGE POND DESIGN

The following information shall apply to Standard Regional Pond Design.

Design Requirements

Pond design shall be in conformance with the current NDPDES permit.

Minimum pond design shall be for a 100-year storm event based upon the most recent NOAA Atlas 14 Point Precipitation Frequency Estimates data, and shall include one (1) foot freeboard. All design modeling shall be done using HydroCAD or equal commercially available modeling software that produces similar model reporting as HydroCAD. The designer shall provide to the City a drainage report signed by a ND Professional Engineer and shall provide an electronic copy of the complete design drainage model.

Drainage and pond modeling shall include 2-, 10-, and 100-year, 24-hour rainfall events as part of the analysis.

The pond design shall include a control outlet structure with emergency overflow design. The overflow structure shall include provisions to prevent overflows from affecting adjoining properties. The outflow and overflow structure shall be designed to prevent plugging, be easily accessible to maintenance personnel, and shall require minimal maintenance. Maximum outflow to a City storm sewer shall be as defined in **Appendices C and D**. The release rate may be less depending on measures needed to meet water quality standards as defined in **Appendix E**. However, the minimum outlet orifice size shall be 4 inches and shall have a screen ahead of the orifice to prevent plugging.

The pond drawdown time criteria is outlined in **Appendix E**.

Geometry

Pond design shall include 15 feet minimum of level ground from the top of back slope of the pond to the property line.

Dry Pond:

1. Slopes shall be 5:1 or flatter up to 15 foot of vertical depth, 6:1 or flatter if 15 foot of vertical depth or greater.
2. 1.5% grade in pond bottom to low flow channel and 0.4% grade from pond inlet to pond outlet with channel liner and 1% grade from pond inlet to pond outlet without channel liner.

3. Dry ponds do not require a safety bench and slope protection armoring if less than or equal to 10 feet deep. Dry ponds do require a safety bench and slope protection armoring if greater than 10 feet deep.
4. Dry ponds require a sloped pond bottom and an underdrain system sufficient to maintain a “dry” state.

Wet Pond:

1. Slopes shall be 6:1 or flatter up to 15 feet of depth. If the designer wishes the pond to be deeper than 15 feet, a geotechnical evaluation of the pond slope stability is required. If the pond backs up to residential homes or legal drains, a geotechnical evaluation of the pond slope stability is also required. The pond shall be designed with safety features such as edge plantings to deter entrance to ponds and a safety ledge or bench at pond perimeter one to two feet below normal water level and extend out 10 feet before continuing on slope.
2. Slope protection shall be installed to one foot below safety bench, or one foot above and one foot below normal water level, whichever is greater. The slope protection shall be riprap or turf reinforcement with seeding.
3. The remainder of exposed slopes shall be turf reinforced and seeded. Rip rap shall meet City of Fargo and NDDOT standards.

All pond aesthetic features such as shape, side slopes, and vegetation that are proposed shall be identified on the plans and match the land area requirements identified in the Zoning Ordinance and project development master plan.

City Ownership of Ponds

The City may take ownership of a stormwater pond that is designed according to the following criteria:

1. To qualify as a regional pond for purposes of City ownership and maintenance, the minimum pond size for a **dry pond shall be 7.5 acre-feet** with a minimum bottom width of 100 feet. The minimum pond size for a **wet pond shall be 15 acre-feet** with an average bottom width of 100 feet. However, the City will review on a case-by-case basis whether a pond qualifies as a regional pond for purposes of City maintenance if its size is smaller than the minimum size identified.
2. A City-owned regional pond should have sufficient right-of-way access for routine and special maintenance as determined by the City Engineer.

3. For ponds to be accepted by the City for maintenance and operation as a regional pond, the features in general shall not result in unusual and/or costly future operation and maintenance, as determined by the City Engineer. Bridges and box culverts, if required, shall meet the design criteria of the regulating authority and shall meet State and Federal safety standards.
4. No fountains or bubblers shall be allowed within City-owned regional wet ponds.

Alternative Design

Ditches, swales, and channels may be designed for a variety of capacities depending on the protection required. When ditches serve as a primary surface water collector in the upper part of a drainage basin, they shall be designed per NDCC 89-14-01 except that as a minimum, shall convey the 10-year storm event without ponding in the roadway or adjacent private property. The City Engineer will ultimately decide if ditches, swales, or channels are allowed in lieu of conventional underground piping.


The City of Fargo Stormwater Service Charge policy identifies credits that may be achieved through building of detention or retention ponds larger than required as determined by this policy. Developers and designers are encouraged to familiarize themselves with the current Stormwater “Determination and Review Policy” for stormwater fees.

NOTES:

- 15' MAX. VERTICAL DEPTH
- MIN. POND SIZE = 7.5 ACRE/FEET
- MIN. 100' BOTTOM WIDTH
- MIN. 1' FREE BOARD FOR 100 YEAR EVENT
- NO BENCH REQUIRED




**DRY POND
(15' MAX. VERTICAL DEPTH)**



**DRY POND
(GREATER THAN 15' VERTICAL DEPTH)**

NOTE:


SIDE SLOPES DISPLAYED WITH 5X VERTICAL EXAGGERATION

 ENGINEERING DEPARTMENT	ORIGINAL: 2019	
	TYPICAL DRY STORM WATER POND DETAIL	
	APPROVED:	DATE:



SIDE SLOPES SHALL BE 6H:1V OR FLATTER FOR POND DEPTHS UP TO 15' VERTICAL


WET POND
(15' MAX. VERTICAL DEPTH)



POND DEPTHS GREATER THAN 15' VERTICAL DEPTH SHALL REQUIRE:


- GEOTECHNICAL EVALUATION
- SLOPE REINFORCEMENT

WET POND
(GREATER THAN 15' VERTICAL DEPTH)




TYPICAL RIP RAP
PLACEMENT

NOTE:
SIDE SLOPES DISPLAYED WITH 5X VERTICAL EXAGGERATION



POND BOTTOM PLAN VIEW
(GREATER THAN 15' VERTICAL DEPTH)



POND BOTTOM PLAN VIEW
(15' MAX. VERTICAL DEPTH)

APPENDIX G

DESIGN REQUIREMENTS WITHIN SPECIAL ZONES

Southwest Metro Stormwater Design Parameters and Pond Coverage

The following information shall apply to the coverage area for the new Southwest Metro Stormwater Pond. Properties that develop in the area shown will have regional stormwater detention and stormwater quality coverage managed by the City of Fargo. Maps of the drainage boundaries and conceptual design are found in this Appendix.

Fargo has moved forward since 2021 to construct the Lift Station and the first phase of the Southwest Metro Stormwater Pond. Drainage ditches and storm sewer piping within public rights-of-way and easements are being installed as properties and streets develop. Interim measures may be necessary to be constructed while the larger system is being fully designed and developed, due to a proposed improvement parcel's location and distance from currently completed conveyance system components. This stormwater master planning will allow properties within the area outlined to build without meeting discharge and water quality requirements outlined in this Design Policy.

However, developing properties will need to be aware that the City of Fargo designs their street storm sewers for a 2-year rainfall event on local streets and 5-year rainfall event on arterial streets, and developing properties shall design their sites to account for the limited street conveyance of stormwater if not directly discharging to the conveyance ditch system or the pond.

Downtown Mixed Use Zoning (DMU) Requirements for Stormwater

A modification to the stormwater retention policy for the existing areas classified as within the Downtown Mixed Use zoning district as of July 27, 2015 is as follows: Any development on a parcel one acre in size or larger within the DMU shall be allowed a maximum stormwater runoff rate that is not greater than the existing condition's runoff rate from the parcel for the 2-, 10- & 100-year, 24-hour synthetic rainfall events. No stormwater retention will be required on the parcel unless necessary to maintain the runoff rate below the existing (pre-development) runoff rate. Lots under one acre are exempt from the retention requirements.


This modified policy does not affect the North Dakota Department of Environmental Quality's water quality requirements. Development of all parcels within the DMU are still required to follow, as applicable, the water quality requirements set by the DEQ.

For parcels completing a zoning change to DMU after the effective date of July 27, 2015, property improvements shall meet all stormwater detention and water quality standards per the policy.

New Developments with Regional Detention and Special Release Rates

This section applies to new developments with Site Amenities Plans or Developer's Agreements that provide for regional detention, water quality, and design release rates that differ from the normal requirements covered in this design policy.

The most recent and complete record of these special design areas is available on the City of Fargo public GIS site. The GIS layer to be displayed is "StormPolicyDesignDeviations" with the modified design requirements notated within the differentiated areas.



52nd Avenue S

VETERANS BLVD S

Cass County Drain 27

Future Development Area
Area = 2,325 Acres

64th Avenue S

Cass County Drain 53

45th Street S

76th Avenue S

42nd Street S

76th Avenue S

Existing Drain 27 Drainage Area
Area = 3,031 Acres

Existing Drain 53 Drainage Area
Area = 1,503 Acres

Interstate-29

88th Avenue S

88th Avenue S

100th Avenue S

100th Avenue S

Legend

- Legal Drains
- Future Development Drainage Area
- Existing Conditions Drainage Area





Figure 1: Study Drainage Boundaries

Title	Author	Scale	Project No.	Date	Sheet
AS 50000	03/17/2010	1" = 100'	088-001	11/10	1 of 1

Houston Engineering Inc.



SEAL

REVISED


Figure 3



PRELIMINARY
Not for Construction

OPTION 2	STORMWATER MASTER PLAN
PROJECT FM-XX-XX	
DESIGN BY: [blank]	CHECKED BY: [blank]
DRAWN BY: [blank]	DATE: 12-11-18
CITY OF	SECTION NO.
Fargo	1
	SHEET NO.
	2 of 2


DMU July 27, 2015



Legend

- Other
- DMU - Downtown Mixed Use

Summary of Storm Sewers in Use



Fargo Storm Sewer System

Area = 50 square miles

Storm Lift Stations = 82

**Storm
Sewer**

Does the stormwater system connect to the City of Fargo system?
If not tied into the City system, is proper documentation for not connecting indicated?
Is the pipe the correct size and type?
is the pipe at the correct grade? Does it flow correctly?
Are inlets and manholes appropriately located and spaced?
Is Reinforced Concrete Pipe (RCP) used under pavement in the City Right-of-Way?
If boring under the street - may use C900 pipe with adequate depth.
Are pond outlet structures located outside the 10' Utility easement?
Is there a note stating to call the Inspections Dept. for an inspection of the connection to the City storm system?
Ensure storm sewer does not conflict with other underground utilities.

Section 20-0608
Spec Section 1500
Spec Section 1500
Spec Section 1500
Submittal
Submittal

Grading

Is there a Grading Plan?
Does the grading plan clearly indicate (arrows and/or elevations) where all site storm water flows?
Is there a 0.5 foot elevation difference between the sidewalk and curb?
Is the elevation 15 feet from structures at BFE or above (check pond slopes)?
Are maximum recommended pond slopes (4:1) exceeded?

Submittal
Submittal
Submittal
Submittal
Submittal

**Storm
water**

Are HydroCAD (or similar) stormwater model results for the 2 and 100 year storm events included in the submittal?
Does the project involve over 1,000 SF of parking lot?
Is the project part of a previously approved larger stormwater plan?
Does site imperviousness meet the approved plan parameters?
Is on-site storm water detention required?
Do detention volumes and discharge rates meet requirements? Check min. 4" orifice
Is there a 24 -72 hour drawdown period for the 2 year event? Or, is there a "Defender" device?

Submittal
Submittal
Submittal
Submittal
Detention Policy
Detention Policy
State water quality

ESC/SWPPP

Is there an Erosion and Sediment Control Plan?
Does the Erosion and Sediment Control (ESC) plan include all necessary ESC measures?
Does the Erosion and Sediment Control plan include all the appropriate and necessary details?

Submittal
Submittal
Submittal

Paving


Is there a Paving Plan?
Does the paving plan clearly indicate paving types and locations?
Is street access appropriate for the pavement functional classification (arterial, collector, local)?
Do driveway widths, placement (spacing), and thickness meet requirements?
Do patches match existing pavement sections?

Submittal
Submittal
Section 20-0702
Submittal



POND POINTS

- POND
- DETENTION POND
- RETENTION POND
- BIORETENTION POND
- UNDERGROUND STORAGE



STORM PONDS PER ZONE

- ZONE 1 = 118
- ZONE 2 = 119
- ZONE 3 = 99
- ZONE 4 = 129
- ZONE 5 = 85



Standard Operating Procedure (SOPs) for Stormwater Pond Inspections

Procedure

At a minimum, 20% of all Stormwater ponds will be inspected each year on a rotating basis with all ponds inspected before the expiration of the NDR04-0000 MS4 Permit.

- Pond Inventory (January 2024)
 - City of Fargo – 59 ponds
 - Fargo Park District – 59 ponds
 - County Owned – 4 ponds
 - Privately owned – 368 ponds
- The Storm Sewer Utilities Engineer shall manage a list of City-owned/private ponds.
- GIS will be updated when new ponds are constructed or modified.

Inspections

- Staff will visually inspect all of the ponds and end sections of the pipes draining into them at least once during a five year cycle of the NDR04-0000 MS4 Permit.
 - The goal is to inspect 20% of the drainage system each year.
 - All records shall be kept at T:\Engineering\StormMgmt\Stormwater Management\MS4 - Discharge Permit\PERMIT ADMIN\Pond Inspections

Corrective Action

- Slope/Bank erosion
 - Depending on severity submit a work order to the Public Works Supervisor.
- Blocked or damaged infrastructure
 - Report to Public Works Supervisor with report for cleaning, repair or replacement needs as their schedule allows.



Standard Operating Procedure (SOPs) for Water Quality Device

Procedure

Inspect all water quality devices and underground storage systems at least once every two years on a rotating basis in compliance with the NDR04-0000 MS4 Permit.

- Water Quality Device inventory (January 2024)
 - City of Fargo – 5 WQ devices
 - Privately owned – 103 WQ devices
- The Storm Sewer Utilities Engineer shall manage a list of City-owned/private Water Quality Devices.
- Records of newly added Water Quality Devices will be updated via spreadsheet when they are constructed or modified.

Inspections

- Staff will visually inspect all Water Quality Devices at least once every two years on a rotating basis in compliance with the NDR04-0000 MS4 Permit.
 - The goal is to inspect 50% of structures each year
 - Inspections will consist of structural condition, inflow points, pollution capture functions, sediment levels
 - All records shall be kept at T:\Engineering\StormMgmt\Stormwater Management\MS4 - Discharge Permit\PERMIT ADMIN\Private_WQ_Maintenance

Corrective Action

- Sediment Levels
 - Sediment levels will require cleaning/removal depending on the manufacturer's recommended O&M manual.
- Damaged infrastructure
 - Repair or replacement shall be required according to the manufacturer's recommended O&M manual.
 - All city owned water quality devices shall be maintained annually regardless of the manufacturer's recommended O&M manual



Public Works Maintenance Operations

All Public stormwater features are inspected on a rotational basis annually for function, maintenance or repair by the public works/engineering departments. Those inspections resulting in major repair are forwarded to the engineering department for evaluation. Ponds and basins are inspected during maintenance activities, lined channels are cleaned and inspected annually, outfalls (and lift stations) are inspected both fall and spring.

Drain Cleaning



This department also conducts a street sweeping program on a continuous basis during non-winter months. Salt storage/fueling operations are covered and not exposed to precipitation. Salt application management continues to use technology to minimize usage. See specific MS4 requirement comments below.

Training

Stormwater training is provided to appropriate city departments and their staff on a rotating basis. SSU curriculum compliments existing department training with a stormwater validation. Most departments have their own unique training for tasks on discipline specific topics that become uniformed operational standards. Recognize, respond and report are common themes in municipal operations. Remarkably, much of their "operational" training is stormwater connected. Some examples of the "common interface" are highlighted below along with SSU educational programming for the significant operational areas of the city.

*Conveying the notion "include sound stormwater practice" into
Our everyday operations is beneficial to us all.*

Operations, IDDE Training and Awareness

The stormwater "illicit discharge" is not a new concept to operations. Maintenance operations has traditionally focused on prevention and response to incidents that detract from facility design or function standards. Below are examples of operational scenarios that are also stormwater Best Management Practice (BMP).


- If a vehicle crashed into a drainage ditch, staff discovers it, communicates the incident to a supervisor and it gets removed (under an operational directive). Cleanup is a typical duty of operations, but it is also part of the stormwater concept of IDDE. Emphasizing the need to reduce the discharge of fluids and other contaminants from such situations personifies the stormwater educational goal.
- Non-conforming sewer connections, discharges, etc., discovery, awareness, and remediation is a routine operational task. Stormwater training merely serves as a reminder to continue good operational drill because it doubles as good stormwater practice.
- Material spills training in a department's safety protocol also has a direct correlation to stormwater. Protect the employee, pairs as a stormwater BMP by the training emphasis to follow manufacturer's instructions on the use of maintenance chemicals (mixing and application).

Mowing Operations

Consider the practicality of mower discharges placed back onto the turf, an acknowledged stormwater BMP. Yet, operational execution validates that collecting, hauling and dumping the clippings imposes added work and cost which effectively eliminates the option from consideration. Following that same premise, discharging clippings into the gutter only to later retrieve the same clippings from a capacity diminished, conveyance features is illogical. Given the absoluteness of such a fact, stormwater training simply needs to accentuate a correlation.

Snow Removal Operations

Snow removal occurs on a 24/7 basis following prescribed procedures and routes. Snow is hauled to an approved dump site citywide (Mapped). These snow dump sites all have adequate grass buffers that function as BMPs and are inspected twice each season (fall & spring). Department training on the most efficient routes, dumpsite perimeter control and area limits, the stormwater education aspect is also fulfilled.

 Snow Dump Inspections 2023						
Location	Date	Time	Stormwater Conveyance	Report of Findings (condition of site)	Action to be taken	Additional Comments
12 Ave/35 St N	5/16/2023	1:23 PM	City Storm Sewer System	Fair - Good	dry out clean debris	Snow pile is still quite large
12 Ave/35 St N	9/5/2023	2:25 PM	City Storm Sewer System	Very Good	None	None
6251 36 St S	5/16/2023	2:43 PM	City Storm Sewer System	Very Good	dry out clean debris	Site is also stockpiling asphalt millings
6251 36 St S	9/7/2023	8:52 AM	City Storm Sewer System	Very Good	None	None
3837 38 St S	5/16/2023	2:33 PM	City Storm Sewer System	Very Good	dry out clean debris	Snow pile is almost gone
3837 38 St S	9/7/2023	8:25 AM	City Storm Sewer System	Very Good	None	Site is being used for a lay down yard for Project #NR-23-A1
3 Ave N & 45 St N	5/16/2023	1:28 PM	City Storm Sewer System	Very Good	dry out clean debris	Much of the snow pile is draining toward the street. Snow pile is still quite large
3 Ave N & 45 St N	9/5/2023	2:17 PM	City Storm Sewer System	Good	Drainage	Some melting does drain toward street
5400 63 St S	5/16/2023	2:22 PM	County Drain #27	Very Good	None	This site isn't used as often yet. Snow pile is gone.
5400 63 St S	9/7/2023	8:39 AM	County Drain #27	Very Good	None	None
450 34 St S	5/16/2023	1:52 PM	County Drain, Storm sewer system	Very Good	Still very wet. Needs to dry out and be cleaned of debris	Snow pile is almost gone
450 34 St S	9/5/2023	3:00 PM	County Drain, Storm sewer system	Good	None	The existing snow dump is under construction from Cass county jail addition

Land Disturbing Activity

Land disturbing activity abides by Section 3300 of the City of Fargo Standard Specification criteria for stormwater management and erosion control.

SECTION 3300
<p>CITY OF FARGO SPECIFICATIONS EROSION AND SEDIMENT CONTROL</p>
<p>PART 1 DESCRIPTION OF WORK</p>
<p>The work to be completed under this section of the Specifications and the accompanying plans shall include all labor, materials, and equipment necessary to provide for Erosion and Sediment control on City</p>

Storm Sewer Conveyance Maintenance Operations

Storm sewer maintenance continues perpetually on a rotational or as required basis. The supervisor schedules inspections and directs maintenance work orders. Public works maintenance platform includes inspection (camera), minor repairs, surface sweeping, pipe jetting, mowing, open channel sediment removal and prescribed lift station O & M work.

Roadway Maintenance Operations

Roadway maintenance activities consist of a sweeping program and minor repairs (mill/seal, mud jacking, pothole, etc.)

Standard Operating Procedures, Guides and Policies (Written)

See written procedure examples for maintenance at the end of this section.



Sweeping 2023		
Zone	Tonnage	Times per Year
1	317.26	10
2	177.15	11
3	170	12
4	104	14
5	150.67	9
6	382	5
7	334	6
8	320.51	13
9	232.31	14
10	89.38	9
11	262.02	5
12	176.1	5
13	196.73	9
14	107.1	11
15	201.34	10
16	91.59	9
17	135.84	5
1P	258	12
2P	317.41	6
3P	232.18	4
Total	4255.59	



1. PRODUCT AND COMPANY IDENTIFICATION

Product Identity: AMP

Recommended use of the chemical and restrictions on use: Road anti-icing and de-icing

Manufacturer: EnviroTech Services, Inc.
910 54th Ave, Suite 230
Greeley, CO 80634

Telephone: (970) 346-3900

Emergency Phone: CHEMTREC: (800) 424-9300

SDS Date of Preparation: 8/24/2017

2. HAZARDS IDENTIFICATION

GHS Classification:

Physical	Health	Environment
Not Hazardous	Not Hazardous	Not Hazardous

GHS Label Elements:

None Required

3. COMPOSITION/INFORMATION ON INGREDIENTS

Component	CAS No.	Amount
Water	7732-18-5	Balance
Magnesium Chloride	7791-18-6	13-23%
Proprietary Corrosion Inhibitor Blend	Proprietary	Proprietary

The exact concentration is being withheld as a trade secret.

4. FIRST AID MEASURES

Eye: Flush victim's eyes with large quantities of water, while holding the eyelids apart. Get medical attention if irritation occurs and persists.

Skin: Wash skin thoroughly with soap and water. Get medical attention if irritation develops. Remove and launder clothing before reuse.

Ingestion: Do not induce vomiting. Rinse mouth with water and give one glass of water to drink. Never give anything by mouth to an unconscious or convulsing person. Get medical attention if symptoms develop.

Inhalation: Remove victim to fresh air. If breathing is difficult or irritation persists, get medical attention.

Most important Symptoms: May cause slight eye and skin irritation.

Indication of immediate medical attention/special treatment: Immediate medical attention is not required.

5. FIRE FIGHTING MEASURES

Suitable (and Unsuitable) Extinguishing Media: Use media appropriate for surrounding fire. Cool fire exposed containers and structures with water.

Specific hazards arising from the chemical: Thermal decomposition may yield hydrogen chloride, halogenated compounds, and chlorine gas.

Special Protective Equipment and Precautions for Fire-Fighting Instructions: Firefighters should wear positive pressure self-contained breathing apparatus and full protective clothing. Aqueous solutions may cause surfaces to be extremely slippery and cause a slip hazard.

6. ACCIDENTAL RELEASE MEASURES

Personal Precautions, Protective Equipment, and Emergency Procedures: Wear appropriate protective clothing as described in Section 8. Wash thoroughly after handling.

Methods and Materials for Containment and Cleaning Up: Dike and collect liquid or absorb with an inert absorbent and place in appropriate containers for disposal. Flush spill area with water. Report releases as required by local, state and federal authorities.

7. HANDLING AND STORAGE

Precautions for Safe Handling: Avoid contact with the eyes, skin and clothing. Avoid breathing mists or aerosols. Wear protective clothing and equipment as described in Section 8. Wash thoroughly with soap and water after handling. Keep containers closed when not in use.

Conditions for Safe Storage, Including Any Incompatibilities: Store in a cool, dry, well-ventilated area away from incompatible materials. Product may be corrosive to some metals.

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

Exposure Guidelines:

Water	None Established
Magnesium Chloride	None Established
Proprietary Corrosion Inhibitor Blend	None Established

Engineering Controls: Use with adequate general ventilation to minimize exposures.

Respiratory Protection: In operations where exposure levels are excessive, a NIOSH approved respirator with dust/mist cartridges or supplied air respirator appropriate for the form and concentration of the contaminants should be used. Selection and use of respiratory equipment must be in accordance with OSHA 1910.134 and good industrial hygiene practice.

Skin Protection: Wear impervious gloves such as rubber or neoprene if needed to avoid prolonged skin contact.

Eye Protection: Safety glasses recommended.

Other: Long-sleeved clothing and long pants recommended to avoid prolonged skin contact. Suitable washing facilities should be available in the work area.

9. PHYSICAL AND CHEMICAL PROPERTIES

Appearance And Odor: Clear to slight yellow liquid with low or no odor.

Physical State: Liquid	Odor Threshold: Not established
Vapor Density: Not determined	Initial Boiling Point/Range: Not Determined
Solubility In Water: Soluble	Vapor Pressure: Not determined
Relative Density: 1.27-1.31	Evaporation Rate: Not determined
Melting/Freezing Point: Equal to or lower than -15°F (-26°C)	pH: 6.5 - 9
VOC Content: Not determined	Octanol/Water Coefficient: Not determined
Solubility: Complete	Decomposition Temperature: Not determined
Viscosity: <200 cP @ 0°F	Flammability (solid, gas): Not applicable
Flashpoint: None	Autoignition Temperature: Not determined
Flammable Limits: LEL: Not determined	UEL: Not determined

10. STABILITY AND REACTIVITY

Reactivity: Not normally reactive

Chemical Stability: Stable under normal storage and handling conditions.

Possibility of Hazardous Reactions: None known.

Conditions to Avoid: None known.

Incompatible Materials: Strong oxidizing agents, concentrated acids, and some metals.

Hazardous Decomposition Products: When heated to decomposition emits hydrogen chloride, halogenated compounds, and chlorine gas.

11. TOXICOLOGICAL INFORMATION

HEALTH HAZARDS:

Ingestion: Ingestion may cause slight irritation with nausea, vomiting, and diarrhea.

Inhalation: Inhalation of mists may cause slight irritation of the nose, throat, and upper respiratory tract.

Eye: May cause slight irritation with pain and tearing.

Skin: May cause slight irritation on prolonged or repeated contact.

Sensitization: This material is not known to cause sensitization.

Chronic: None known.

Carcinogenicity: None of the components is listed as a carcinogen or suspected carcinogen by IARC, NTP, or OSHA.

Germ Cell Mutagenicity: None currently known.

Reproductive Toxicity: None currently known.

Numerical Measures of Toxicity:

No toxicity data available

12. ECOLOGICAL INFORMATION

Ecotoxicity: Fathead minnow NOEC: 3.00 g/L; Ceriodaphnia dubia NOEC: 3.00 g/L; Selenastrum growth NOEC: 3.00 g/L.

Persistence and Degradability: Biodegradation is not applicable to inorganic substances.

Bioaccumulative Potential: No data available

Mobility in Soil: No data available

Other Adverse Effects: None known

13. DISPOSAL CONSIDERATIONS

Dispose in accordance with local, state, and federal environmental regulations.

14. TRANSPORT INFORMATION

DOT Hazardous Materials Description:

Proper Shipping Name: Not regulated

UN Number: None

Hazard Class/Packing Group: None

Labels Required: None

15. REGULATORY INFORMATION

CERCLA: This product is not subject to CERCLA release reporting. Many states have more stringent release reporting requirements. Report spills required under federal, state and local regulations.

SARA Hazard Category (311/312): Refer to Section 2 for OSHA Hazard Classification.

SARA 313: This product contains the following chemicals subject to Annual Release Reporting Requirements under SARA Title III, Section 313 (40 CFR 372): None

EPA TSCA Inventory: All of the ingredients in this product are listed on the EPA TSCA Inventory.

CANADA:

This product has been classified under the CPR and this SDS discloses information elements required by the CPR.

Canadian CEPA: All the components of this product are listed on the Canadian DSL.

16. OTHER INFORMATION

NFPA Rating: Health = 1 Flammability = 0 Instability = 0
HMIS Rating: Health = 1 Flammability = 0 Physical Hazard = 0

SDS Revision History:

5/10/2017: New SDS

6/23/2017: Revised Sections 12, 15.

8/24/2017: Revised Section 9.

Disclaimer: *This Safety Data Sheet (SDS) is provided in response to customer requests to address the safe handling of the product. All statements, technical information and recommendations contained herein are the best of our knowledge, reliable and accurate. This SDS is not intended to make any representation as to how the product will perform when used for its intended purpose by a user. In that regards the product is sold "AS IS" and nothing in this SDS should be deemed to be a representation or warranty of any injury, loss, or damage, of any kind or nature, which are sustained by or arise from the use of the product. Nothing in this SDS is intended to be a representation or warranty by the manufacturer of the accuracy, safety, or usefulness for any purpose of any technical information, materials, techniques, or practices.*

The information contained in this Safety Data Sheet is, to the best of our knowledge, accurate and reliable. This information should be provided to all individuals handling this product. Federal, state, and local regulations should be followed when handling this product.



Sewer By-Pass Procedure

Log discovery / notice and direct to appropriate department / staff

Receive work order assignment from dispatcher / supervisor.

Organize performance / safety equipment and deploy to field.

Site Assessment

- Ensure personal safety
- Assess problem / scope of repair

Notify affected departments / staff

- Environmental Health 476-6729
- Public Works 241-1453
- Stormwater 241-1545
- Wastewater Treatment Plant (immediately report any sanitary discharge) 241-1545
- Water Filtration Plant 241-1469

Public Safety

- Take action to assure public safety / traffic control / Public Notice

Perform Work

- Discharge to a like facility if possible
- Setup emergency pumping operation
- Take action to reduce downstream effect
- Document with photos, notes

Post Action

- Log on location map / site & discharge point(s)
- Note suggestions for mitigation

Procedure implementation/revision date

Supervisor

DRAIN CLEANING 2023

<u>Drain Location</u>	<u>Date Cleaned</u>	<u>#of Loads</u>	<u>Total Weight in Tons</u>
Drain #10	8/1/2023 - 8/2/2023	7	72
Drain #3	7/26/2023 - 7/31/2023	14	166.38
Drain #40	8/18/2023	27	294
Osgood	7/20/2023	1	9.5
Amber Valley PKWY & 51st St S.	7/24/2023	1	5
Amber Valley PKWY & 55th St S.	7/24/2023	1	1
41st St & 30th Ave S. (SW & NE)	7/20/2023	1	4
23rd Ave & 26th St S.	7/19/2023	1	6.8
North Oaks	7/24/2023	1	4
Drain #27 (Ulteig ENG.)	7/17/2023 - 7/19/2023	6	58.1
34th St North OF 7th Ave N.	7/24/2023	1	2
Action 7th Ave & 36th St N.	7/24/2023	1	1
Pepsi Drain	7/24/2023	1	4
48th St & 15th Ave S. (Scheel's)	7/24/2023	1	4
Aggregate Dr.	7/24/2023	1	0.5
Big Top Bingo Pond	7/20/2023	1	0.5
Luther Ford Holding Pond	7/19/2023	1	6.8
4495 53rd St S. West Side	7/20/2023	1	0.5
Drain #40 (Fisheye)	7/20/2023	1	9.5
25th St S. 6700 BLK (East Side Davies)	7/19/2023	1	6.8
Roers Holding Pond	7/20/2023	1	9.5
		TOTAL	64
			665.88

small bucket



Mowing Maintenance

Receive work order assignment from supervisor.

Organize performance / safety equipment, load maintenance materials and deploy.

Direct clipping discharges back onto lawn and away from storm water conveyances.

Follow manufacturer's instructions for all chemical use.

Record any required end of task reports.

Procedure date

Supervisor

Stormwater Pollutants

As defined by City of Fargo Code of Ordinances Chapter 37-0102.33 (Stormwater Ordinance)

Group	Examples				
Dumping (A)	<ul style="list-style-type: none"> <li style="width: 33%;">• Debris <li style="width: 33%;">• Grass Clippings <li style="width: 33%;">• Vegetative Materials <li style="width: 33%;">• Rocks <li style="width: 33%;">• Earth Fill <li style="width: 33%;">• Concrete Chunks <li style="width: 33%;">• Metal <li style="width: 33%;">• Tree Branches <li style="width: 33%;">• Other Construction Materials 				
Disposal/Misuse (C)	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; border: none;"><u>Chemicals:</u></td> <td style="width: 33%; border: none;"><u>Petroleum Based Products:</u></td> </tr> <tr> <td style="border: none;"> <ul style="list-style-type: none"> • Fertilizers • Pesticides </td> <td style="border: none;"> <ul style="list-style-type: none"> • Herbicides • Gasoline/Fuels • Solvents • Oil • Paints </td> </tr> </table>	<u>Chemicals:</u>	<u>Petroleum Based Products:</u>	<ul style="list-style-type: none"> • Fertilizers • Pesticides 	<ul style="list-style-type: none"> • Herbicides • Gasoline/Fuels • Solvents • Oil • Paints
<u>Chemicals:</u>	<u>Petroleum Based Products:</u>				
<ul style="list-style-type: none"> • Fertilizers • Pesticides 	<ul style="list-style-type: none"> • Herbicides • Gasoline/Fuels • Solvents • Oil • Paints 				
Sediment (D)	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; border: none;"><u>Migration To:</u></td> <td style="width: 33%; border: none;"></td> </tr> <tr> <td style="border: none;"> <ul style="list-style-type: none"> • City Streets • Stormwater Conveyance System </td> <td style="border: none;"> <ul style="list-style-type: none"> • Private Properties • Failure to Remove Sediment Tracked by Construction Traffic </td> </tr> </table>	<u>Migration To:</u>		<ul style="list-style-type: none"> • City Streets • Stormwater Conveyance System 	<ul style="list-style-type: none"> • Private Properties • Failure to Remove Sediment Tracked by Construction Traffic
<u>Migration To:</u>					
<ul style="list-style-type: none"> • City Streets • Stormwater Conveyance System 	<ul style="list-style-type: none"> • Private Properties • Failure to Remove Sediment Tracked by Construction Traffic 				



Outfall Inspection Procedure

Receive work order assignment from supervisor.

Organize performance/safety equipment and deploy to field.

Perform inspections as directed by the supervisor / Outfall Inspection Form:

- Ensure personal safety
- Complete check-off list and/or comment on irregularities
- Maintain trash rack
- Take a minimum of one digital photo
- Observe up/down stream conditions
- Mark and cordon-off all confirmed or suspect pipe separation locations to a safe level
- Maintain wet well (clean, pump, etc.)
- If Illicit Discharge is observed, follow IDDE Procedure
- Submit completed forms to supervisor
- Maintenance required tracking sheet delivered to engineering for repairs

Trace-back (suspect flow, IDDE, aggregate materials, etc.,) as directed by supervisor

- Isolate location via ascending manhole inspection
- Use direct method (smoke, dye, etc.) to detect origination/source
- Contain, stop discharge and notify owner/occupant to attain conformance
- Obtain/restore compliance

Procedure implementation/revision date

Supervisor

Storm Outfall Inspections - Change year of inspection to the right >


Select Date of Inspection
2023 Outfall Inspection

OUTFALL INSPECTIONS

- 21st Ave. S & 5th st s
Overall Outfall Rating: Poor
- 26th Ave. S country club dr.
Overall Outfall Rating: Poor
- Lift Station 27
Overall Outfall Rating: Poor
- 3702 10 st n
Overall Outfall Rating: Fair
- Kandi Lane N
Overall Outfall Rating: Fair
- Edgewood Golf Course
Overall Outfall Rating: Fair
- 29 th ave & north oaks
Overall Outfall Rating: Fair
- 28th Ave. N
Overall Outfall Rating: Fair
- Lift Station 73
Overall Outfall Rating: Fair
- 120 North Woodcrest Dr.
Overall Outfall Rating: Fair
- North Woodcrest Drive N & park lane
Overall Outfall Rating: Fair
- Behind VA Hospital
Overall Outfall Rating: Fair
- 15th Ave. N & elm st
Overall Outfall Rating: Fair
- Elm st between 14 th& 15 th ave
Overall Outfall Rating: Fair
- 14th Ave. N & elm st
Overall Outfall Rating: Fair
- 11th Ave. N & elm
Overall Outfall Rating: Fair
- 6th Ave. S & 3rd st
Overall Outfall Rating: Fair
- 10th Ave. S & 4th st
Overall Outfall Rating: Fair
- 12th Ave. S & 4th st
Overall Outfall Rating: Fair


Select from list to filter on map and photos on right.

Last update: 2 minutes ago



City of Fargo, County of Cass, ND, State of North Dakota, Esri, TomTom, Garmin, SafeGraph, METI/NASA, USGS, EPA, NPS, USDA, US... Powered by Esri

Storm Outfall Ratings



1 of 40

OUTFALL DETAILS

Asset ID: STFES0001346

Location: 21st Ave. S & 5th st s

Inspector: Gahner/port

Date Inspected: July 11, 2023


Pipe Separation: Yes

Tash Rack: Yes

Rip Rap: Yes

Comments on Outfall: 5 ft by 4 ft and 6 ft deep

Overall Rating: Poor



Last update: 5 minutes ago



Park & Course Maintenance

Be aware of and minimize water runoff (discharge) into the storm sewer system. Use Best Management Practices (BMPs) to prevent or minimize the identified pollutants (below) from entering the storm sewer system.

Stormwater Pollutants			
<i>As defined by City of Fargo Code of Ordinances Chapter 37-0102.33 (Stormwater Ordinance)</i>			
Group	Examples		
Dumping	<ul style="list-style-type: none"> • Debris • Rocks • Metal 	<ul style="list-style-type: none"> • Grass Clippings • Earth Fill • Tree Branches 	<ul style="list-style-type: none"> • Vegetative Materials • Concrete Chunks • Other Construction Materials
Disposal/Misuse	<u>Chemicals:</u> <ul style="list-style-type: none"> • Fertilizers • Pesticides 	<ul style="list-style-type: none"> • Herbicides 	<u>Petroleum Based Products:</u> <ul style="list-style-type: none"> • Gasoline/Fuels • Solvents • Oil • Paints
Sediment	<u>Migration To:</u> <ul style="list-style-type: none"> • City Streets • Stormwater Conveyance System 	<ul style="list-style-type: none"> • Private Properties 	<ul style="list-style-type: none"> • Failure to Remove Sediment Tracked by Construction Traffic

Receive work order assignment from supervisor.

Read and follow manufacturer's instructions on mixing and application for all fertilizer, herbicide and pesticide maintenance operations. Discuss any concerns with supervisor including post operation cleaning and container disposal.

Organize performance / safety equipment, load maintenance materials and deploy.

Record any required end of task reports.

Procedure date _____

Supervisor _____



Roadway Maintenance Procedure

Receive work order assignment from supervisor.

Organize performance / safety equipment, load maintenance materials and deploy.

Record any required end of task reports.

Procedure date

Supervisor



1. PRODUCT AND COMPANY IDENTIFICATION

Product Identity: Salt Brine with AMP®

Chemical Name: Sodium chloride solution plus proprietary salt brine enhancer.

Recommended use of the chemical and restrictions on use: Road anti-icing and de-icing.

Manufacturer: EnviroTech Services, Inc.
910 54th Avenue Suite 230
Greeley, CO 80634

Telephone: (970) 346-3900

Emergency Phone: CHEMTREC: (800) 424-9300

SDS Date of Preparation: 7/18/2017

2. HAZARDS IDENTIFICATION

GHS Classification:

Physical	Health	Environment
Not Hazardous	Not Hazardous	Not Hazardous

GHS Label Elements:

None Required

3. COMPOSITION/INFORMATION ON INGREDIENTS

Component	CAS No.	Amount
AMP® Proprietary Enhancer	Proprietary	5 - 25%
Sodium Chloride	7791-18-6	15-22%
Magnesium Chloride	7786-30-3	0.5-3.25%
Calcium Chloride	10043-52-4	0.4-2%
Water	7732-18-5	Balance

The exact concentration of is customer dependent.

The exact concentration of the AMP Enhancer is being withheld as a trade secret.

4. FIRST AID MEASURES

Eye: Flush victim's eyes with water while holding the eyelids apart. Get medical attention if irritation occurs and persists.

Skin: Wash skin thoroughly with soap and water. Get medical attention if irritation develops. Remove and launder clothing before reuse.

Ingestion: Do not induce vomiting unless directed to do so by a medical professional. Rinse mouth with water and give one glass of water to drink. Do not give liquids to an unconscious person. Get medical attention if symptoms develop.

Inhalation: If symptoms occur, remove victim to fresh air. If breathing is difficult or irritation persists, get medical attention.

Most important Symptoms: May cause slight eye irritation. Dust may cause slight respiratory tract irritation.

Indication of immediate medical attention/special treatment: Immediate medical attention is not required.

5. FIRE FIGHTING MEASURES

Suitable (and Unsuitable) Extinguishing Media: Use media appropriate for surrounding fire. Cool fire exposed containers and structures with water.

Specific hazards arising from the chemical: Thermal decomposition may yield chloride gas, oxides of carbon and sodium, and other harmful or irritating chemicals.

Special Protective Equipment and Precautions for Fire-Fighting Instructions: Firefighters should wear positive pressure self-contained breathing apparatus and full protective clothing. Aqueous solutions may cause surfaces to be extremely slippery and cause a slip hazard.

6. ACCIDENTAL RELEASE MEASURES

Personal Precautions, Protective Equipment, and Emergency Procedures: Wear appropriate protective clothing as described in Section 8. Wash thoroughly after handling.

Methods and Materials for Containment and Cleaning Up: Sweep up material and collect in a suitable container for disposal. Flush spill area with water. Report releases as required by local, state, and federal authorities.

7. HANDLING AND STORAGE

Precautions for Safe Handling: Avoid contact with the eyes, skin, and clothing. Avoid breathing dusts. Wear protective clothing and equipment as described in Section 8. Wash thoroughly with soap and water after handling. Keep containers closed when not in use.

Conditions for Safe Storage, Including Any Incompatibilities: Store in a cool, dry, well-ventilated area away from incompatible materials.

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

Exposure Guidelines:

AMP	None Established
Sodium Chloride	None Established

Engineering Controls: Use with adequate general ventilation to minimize exposures.

Respiratory Protection: In operations where exposure levels are excessive, a NIOSH approved respirator with dust cartridges or supplied air respirator appropriate for the form and concentration of the contaminants should be used. Selection and use of respiratory equipment must be in accordance with OSHA 1910.134 and good industrial hygiene practice.

Skin Protection: Wear impervious gloves such as rubber or neoprene if needed to avoid prolonged skin contact.

Eye Protection: Safety glasses recommended.

Other: Long-sleeved clothing and long pants recommended to avoid prolonged skin contact. Suitable washing facilities should be available in the work area.

9. PHYSICAL AND CHEMICAL PROPERTIES

Appearance And Odor: Clear, colorless liquid. No odor.

Physical State: Liquid	Specific Gravity: 1.15-1.25
Vapor Density: Not determined	Initial Boiling Point/Range: Not established
Solubility In Water: >90% at 20°C	Vapor Pressure: Not determined
Relative Density: Not determined	Evaporation Rate: Not determined
Melting/Freezing Point: Not determined	pH: 6-9
VOC Content: Not determined	Octanol/Water Coefficient: Not determined
Solubility (other): Not determined	Decomposition Temperature: Not determined
Viscosity: <100cP at 20°C	Flammability (solid, gas): Not flammable
Flashpoint: Not applicable	Autoignition Temperature: Not determined
Flammable Limits: LEL: Not determined	UEL: Not determined

10. STABILITY AND REACTIVITY

Reactivity: Not normally reactive.

Chemical Stability: Stable under normal storage and handling conditions.

Possibility of Hazardous Reactions: None known.

Conditions to Avoid: None known.

Incompatible Materials: Strong oxidizing agents, concentrated acids, and some metals.

Hazardous Decomposition Products: When heated to decomposition emits carbon and sodium oxides, hydrogen chloride, halogenated compounds, and chlorine gas.

11. TOXICOLOGICAL INFORMATION

HEALTH HAZARDS:

Ingestion: Ingestion may cause slight irritation.

Inhalation: Inhalation may cause slight irritation of the nose, throat, and upper respiratory tract.

Eye: May cause slight irritation.

Skin: May cause slight irritation on prolonged or repeated contact.

Sensitization: This material is not known to cause sensitization.

Chronic: None known.

Carcinogenicity: None of the components is listed as a carcinogen or suspected carcinogen by IARC, NTP, or OSHA.

Germ Cell Mutagenicity: None currently known.

Reproductive Toxicity: None currently known.

Numerical Measures of Toxicity:

No toxicity data available

12. ECOLOGICAL INFORMATION

Ecotoxicity: Product: Fathead minnow NOEC: 3.00 g/L; Ceriodaphnia dubia NOEC: 3.00 g/L; Selenastrum growth NOEC: 0.03 g/L

Persistence and Degradability: Biodegradation is not applicable to inorganic substances.

Bioaccumulative Potential: No data available

Mobility in Soil: No data available

Other Adverse Effects: None known

13. DISPOSAL CONSIDERATIONS

Dispose in accordance with local, state, and federal environmental regulations.

14. TRANSPORT INFORMATION

DOT Hazardous Materials Description:

Proper Shipping Name: Not regulated

UN Number: None

Hazard Class/Packing Group: None

Labels Required: None

15. REGULATORY INFORMATION

CERCLA: This product is not subject to CERCLA release reporting. Many states have more stringent release reporting requirements. Report spills required under federal, state, and local regulations.

SARA Hazard Category (311/312): Refer to Section 2 for OSHA Hazard Classification.

SARA 313: This product contains the following chemicals subject to Annual Release Reporting Requirements under SARA Title III, Section 313 (40 CFR 372): None

EPA TSCA Inventory: All of the ingredients in this product are listed on the EPA TSCA Inventory.

CANADA:

This product has been classified under the CPR and this SDS discloses information elements required by the CPR.

Canadian CEPA: All the components of this product are listed on the Canadian DSL.

Canadian WHMIS Classification: Not classified as dangerous.

16. OTHER INFORMATION

NFPA Rating: Health = 0 Flammability = 0 Instability = 0
HMIS Rating: Health = 1 Flammability = 0 Physical Hazard = 0

SDS Revision History:

5/15/2014: New SDS

4/23/2015: Reviewed, no changes needed

4/12/2016: Reviewed, no changes needed

7/18/2017: Reviewed, added Ecotoxicity information

Disclaimer: *This Safety Data Sheet (SDS) is provided in response to customer requests to address the safe handling of the product. All statements, technical information and recommendations contained herein are the best of our knowledge, reliable and accurate. This SDS is not intended to make any representation as to how the product will perform when used for its intended purpose by a user. In that regards the product is sold "AS IS" and nothing in this SDS should be deemed to be a representation or warranty of any injury, loss, or damage, of any kind or nature, which are sustained by or arise from the use of the product. Nothing in this SDS is intended to be a representation or warranty by the manufacturer of the accuracy, safety, or usefulness for any purpose of any technical information, materials, techniques, or practices.*

The information contained in this Safety Data Sheet is, to the best of our knowledge, accurate and reliable. This information should be provided to all individuals handling this product. Federal, state, and local regulations should be followed when handling this product.



Snow Dump Inspections 2023

Location	Date	Time	Stormwater Conveyance	Report of Findings (condition of site)	Action to be taken	Additional Comments
12 Ave/55 St N	5/16/2023	1:23 PM	City Storm Sewer System	Fair - Good	dry out clean debris	Snow pile is still quite large
12 Ave/55 St N	9/5/2023	2:25 PM	City Storm Sewer System	Very Good	None	None
6251 36 St S	5/16/2023	2:43 PM	City Storm Sewer System	Very Good	dry out clean debris	Site is also stockpiling asphalt millings
6251 36 St S	9/7/2023	8:52 AM	City Storm Sewer System	Very Good	None	None
3837 38 St S	5/16/2023	2:33 PM	City Storm Sewer System	Very Good	dry out clean debris	Snow pile is almost gone
3837 38 St S	9/7/2023	8:25 AM	City Storm Sewer System	Very Good	None	Site is being used for a lay down yard for Project #NR-23-A1
3 Ave N & 45 St N	5/16/2023	1:28 PM	City Storm Sewer System	Very Good	dry out clean debris	Much of the snow pile is draining toward the street. Snow pile is still quite large
3 Ave N & 45 St N	9/5/2023	2:17 PM	City Storm Sewer System	Good	Drainage	Some melting does drain toward street
5400 63 St S	5/16/2023	2:22 PM	County Drain #27	Very Good	None	This site isnt used as often yet. Snow pile is gone.
5400 63 St S	9/7/2023	8:39 AM	County Drain #27	Very Good	None	None
450 34 St S	5/16/2023	1:52 PM	County Drain, Storm sewer system	Very Good	Still very wet. Needs to dry out and be cleaned of debris	Snow pile is almost gone
450 34 St S	9/5/2023	3:00 PM	County Drain, Storm sewer system	Good	None	The existing snow dump is under construction from cass county jail addition

